




(050755231)

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

Locate Well Correctly

- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report

x			
	34		

Notice to do work Land: Fee and Patented
 Report of work done State Lease No. C-1072

Colorado State Logan County Sterling Area No. 15 Field

1 (Well No.) D. A. Hamil (Lease) 30 - NW 34 7N 52W --
 (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 1985 Ft. (N) of Section Line and 658 Ft. (E) of West
 Section Line. (S) (W)

The elevation above sea level is 4175 Ft. KB

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- 11- 3-54 Spudded and cemented 7" casing at 278 with 100 sacks regular cement.
- 11-10-54 Drill Stem Test No. 1 - 4480-4510' open 1 hour with weak blow, died in 35 minutes; reset tool after 40 minutes with weak blow, died in 7 minutes, recovered 97' mud. IFP 0, FFP 0, shut in 30 minutes, BHP 1060.
- 11-12-54 Ran Schlumberger ES and Microlog. Ran heavy mud from total depth (4691) to 293', cement from 293-263', mud from 263-10', cement from 10' to surface in such a manner as not to interfere with surface cultivation. D&A.

COMPLETE

Schlumberger Formation Tops:
 Niobrara 3680 (+495)
 Base Niobrara 4036 (+139)
 Base Codell 4040 (+135)
 Greenhorn 4218 (- 43)
 Bentonite Marker 4390 (-215)
 Muddy 4479 (-304)
 Dakota 4572 (-397)

AJJ	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	<input checked="" type="checkbox"/>
FILE	

Approved: NOV 26 1954

Date November 23, 1954

[Signature]
 Director

Company Shell Oil Company

Address 1845 Sherman St., Denver, Colorado

By [Signature] R. J. Bauer

Title Acting Division Production Sup't.

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.



P+ca.

T