

DRILLERS WELL LOG

COPY

COPY

COMPANY: A. A. Seeligson

LEASE: Kaepernick #1



SW NE
C-SE-NE, Sec. 25
Twp. 7N, Range 53W,
Logan County, Colorado

0 100 Sand & Gravel
100 130 Blue Shale
130 160 Shale
160 650 Shale
650 1815 Shale
1815 2590 Shale
2590 3090 Shale
3090 3320 Shale
3320 3690 Shale
3690 3889 Shale
3889 3950 Lime & Shale
3950 4085 Shale
4085 4250 Shale
4250 4366 Shale
4366 4400 "D" Sand
4400 4462 Shale
4462 4485 "J" Sand
4485 4542 "J" Sand
4542 Total Depth

COMMENCED: 11-5-54
COMPLETED: 11-13-54

CASING RECORD:

8 5/8" Surface Casing set @ 160'
W/125 Sks of Cement by Halliburton
Dementing Co. 5 1/2" set @ 4514
W/175 Sks cement by Halliburton.

D. S. T.

4387-4433' Tool open 25 min.
Gas to surface 2 1/2 min. Recovered
4,600,000 CMFG per day thru Johnston
DST 3/4" Choke. FP. 620-925 SP. 1210#.

SCHLUMBERGER LOG

Schlumberger log to total depth.

ELEVATION: 3984 K. B.

NOTE: All meas. Kelly Bushing

TOPS: _____ Geologist: Wayne McDaniels _____

Niobrara	3570	(+413)	D-Sand	4366	(-383)
Et. Hays	3891	(+92)	J-Sand	4462	(-479)
Carlile	3940	(+43)	Total Depth	4542	(-559)

(SHUT IN GAS WELL)

STATE OF COLORADO)
COUNTY OF DENVER) SS

I hereby affirm that the above and foregoing is a true and correct copy of
the Kaepernick #1, located C-SE-NE, Sec. 25, Twp. 7N, Range 53W, Logan County,
Colorado.

CONTRACTOR: STRAIN DRILLING CO. (signed)

BY: T. C. Strain (signed)

Subscribed and sworn to before me this 18th day of November, 1954.
My Commission expires September 9, 1958.

(signed) Pat Kessler
Notary Public