




**OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO**



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompleation	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other - Conversion to water injection	<input checked="" type="checkbox"/>

(Check appropriate space)

LEASE NAME Kaepernik "A" WELL NO. 1

FIELD Atwood East WILDCAT -- COUNTY Logan

LOCATION C SW NE Section 25 Township 7N Range 53W Meridian 6th
(Quarter Quarter)

feet from N or S Section Line and feet from E or W Section Line

(DETAILS OF WORK)

Perforated well casing 4385 to 4393 with 4 jets per foot. Packer set @4337'. Annulus loaded with water and casing pressured to 2,000 PSI with no apparent casing leak. Entire perforated interval 4385-96' acidized with 250 gallons 15% MCA. Conversion work completed November 16, 1961. Well redesignated from Kaepernik "A" No. 1 to Atwood East Unit Well No. 11-I.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

NOV 24 1961

Date Nov 24 1961
Director [Signature]

Company Excelsior Oil Corporation Date Nov. 21, 1961

Address Hastings, Nebraska Phone No. 2-2141

By [Signature] Title Vice President
(Signature) S. D. Ford, Jr.