



00621990

DATA SHEET

Operator: J. T. Miers et.al.
Well Name: No. 1 Atkin
Location: SW SE NE, Section 4, 7N-53W
Elevation: 4057 GL 4063 KB
Casing: 8 5/8 set at 107' KB, with 75 sx
Commenced: September 3, 1965
Completed: September 10, 1965
Total Depth: 4816 DPM
Cores: 4765-4816
Logs: No logs run
Hole Size: 7 7/8

FORMATION DEPTHS

Niobrara	3840	Bentonite	4560
Carlite	4210	D Sand	4656 (-593)
Greenhorn	4400	J Sand	4756 (-693)
		J Silt	4732

T D 4816

3/15/66 use as 5 (Frank's) -

- 4500-50 sh gry, 5-7% Ls Lt gry brn, (prob Greenhorn Ls)
tr bent
- 4600 sh gry, tr to 5% Ls as above
- 15 sh gry - 2% Ls as above, tr bent
- 25 sh gry, tr wht Ls, tr Ls Lt brn to gry, fx & shaley
- 50 sh gry, tr grn bent, tr gry bent, scatt
Ls as above
- 70 sh gry, tr Ls Lt gry fx, tr bent Lt gry to wht
- 75 sh gry, tr bent, 5-10% ss Lt gry fg to mg, tight NS
- 80 sh, gry, 10% ss Lt gry fg, poor p&p NS
- 85 sh gry, 35% ss Lt gry fg to vfg, carbip, poor p&p NS
- 90 Same
- 95 Same w/ 5% ssw carb material NS
- 4705 sh gry, 30% ss Lt gry fg, carbonaceous, tight NS
- 10 sh gry, 10% ss aa
- 15 sh gry, 10% ss silty Lt gry fg v carb
- 20 sh gry, 5-10% ss v silty & carb
- 25 sh gry, 5-10% ss Lt gry fg, silty & shaley, ip NS, brn ind claystone
- 35 sh gry, v silty ip, tr ss as above
- 40 sh gry, tr ss as above, 5% silt Lt gry
- 45 sh gry, tr ss Lt gry fg, tr indurated claystone brn, 10% silt
dk gry (d Silt)
- 50 sh gry, tr ss as above, 10% silt dk gry, to brn sdy
- 55 sh gry, 5-10% silt, dk gry brn sdy, tr ss Lt gry fg carb
- 4755-60 sh gry, 2% ss Lt gry fg, NS, 5% silt gry fg sdy
- 65 sh gry, 3% ss Lt gry fg, sl carb ip, poor p&p NS