



99999999

075-05467

Miscellaneous Data

4-7N-53W

Well: #1 Reagan - Fletcher  
Elevation: 4051 Gr., 4061 KB  
Commenced: 11-22-63  
Completed: 11-28-63  
Status: Dry & Abandoned  
Cores: 1: 'J' Sand  
Core Analysis: None  
Drillstem Tests: None  
E-Logs: None  
Surface Casing: 8 5/8" @ 99' cemented  
with 100 sacks

Formation Tops-Sample

Carlile: 4183  
Greenhorn: 4367  
Brown Lime: 4531  
'D' Sand: 4627 (-566)  
'J' Sand: 4715 (-654)  
Total Depth: 4734

Bit Record

<u>Run No.</u>	<u>Size</u>	<u>Make</u>	<u>Type</u>	<u>From</u>	<u>To</u>
1	7 7/8"	Security	S-3	99	2996
2	7 7/8"	Security	S-3	2996	4720
3	7 13/16"	D & S	Diamond	4720	4734

Cores

Core "1": 4720-4734  
Recovered 13 feet

1' Sand, dark gray, very silty, "Reworked", spotty stain and fluorescence.  
12' Sand, gray, very-fine-grained, silty, low P & P, occasional thin shale stringers, no shows.

1' Coring Time

19-29-44-50-60-38-39-36-27-46-30-46-41-51

Formation Description

'D' Sand Sand, gray, very-fine-grained, very silty, low porosity, no shows.  
'J' Sand Circulate @ 4720 - Sand, dark gray, very dirty and silty, fair porosity, spotty stain and fluorescence in 50% of samples.

November 30, 1963

*Robert O. Karl*  
Robert O. Karl



00621999