




COLORADO
LOGAN COUNTY
PAWNEE CREEK



Twp 7N-54W
Section 3
SE NE NW

OPR: Eisenhower Drilg. Co.

WELL #: 1 Whitenbaugh

ELEV: 4136 KB

*TOPS: Elec. Logs Sample

Niobrara 3998
Ft. Hays 4332
G. L. Hays 4580
Timpas 4952
Carlisle 4991
"D" Sand 4842
"J" Sand 4934

DSTS. & CORES:

Cored 4946-4965, Res 11'
tight sand, 2 1/2' hard
med. grained sand,
fair porosity, 3' shaley
sand, 2' med. grained
sand, good porosity
& permeability & stain, 1/2'
med. grained white sand.
No show; DST 4950-65,
Open 1 hr, gas in 15"
rec 400' clean oil,
No water, SIP 1130#,
HP 2610#, FP 0-130#;

SPUD:

TD: 4965 TD PB:
CSG: 10-3/4" @ 211
7" @ 4950

PERF:

BROD. ZONE:

INIT. PROD: Pumped 16 bbls oil
per day.



*For Electric Logs on Rocky Mountain Wells—Ask Us!

990 fnl
330 fel

NEVER PRODUCED
OR SOLD ANY
OIL

P E A