

OFFICE OF STATE OIL INSPECTOR
 SUNDRY NOTICES AND REPORTS OF WELLS
 LOCATED ON PRIVATE LANDS

206-3



(Indicate nature of data by checking below)

- Notice of intention to drill.....
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well..... X
- Report of work done on well since previous report.....

January 8, 1952

Following is a (notice of intention to do work) ~~(notice of intention to do work)~~ (patented) described as follows:
~~(report of work done)~~

Colorado	Logan	Mt. Hope
State	County	Field
8	C. F. Green "B"	NW/4 Section 19
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)
		9N
		53W
		(Range) (Meridian)

The well is located 330 ft. (N) of S Line and 330 ft. (E) of W Line
 (259) (299)

The elevation above sea level is 4209 (GL) ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

We propose to plug and abandon this well by placing heavy mud taken from the bottom of the mud pit from 5160' TD to 5000' where a cement plug will be spotted from 5000' to 4930' opposite the "Muddy" sand which is productive in the Mt. Hope Field. Heavy mud will be placed from 4930' to 191' (bottom of surface casing). A 15' cement plug will be placed at 191'; then heavy mud to within 15' of the surface where a cement plug will be placed to the surface in such a manner that it will not interfere with soil cultivation.

Verbal approval to plug and abandon this well was given to Mr. Wieder (Shell Division Exploitation Engineer) by the office of the Oil and Gas Conservation Commission on January 8, 1952.

Approved: JAN 10 1952

[Signature]
 State Oil Inspector
 DIRECTOR
 Colorado Oil and Gas Conservation Commission

1136 Speer Blvd.
 Denver 4, Colorado

Company Shell Oil Company

Address Denham Bldg., Denver 2, Colo.

By *[Signature]*

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate.