

**FORM
INSP**Rev
X/20**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

07/10/2023

Submitted Date:

07/11/2023

Document Number:

700300643

FIELD INSPECTION FORMLoc ID 333598 Inspector Name: LABOWSKIE, STEVE On-Site Inspection ☐ 2A Doc Num: _____**Operator Information:**

OGCC Operator Number: 8455

Name of Operator: BIG RUN PRODUCTION COMPANY

Address: 318 WEST RUSK

City: TYLER State: TX Zip: 75701

Status Summary:

- ☐ THIS IS A FOLLOW UP INSPECTION
- ☐ FOLLOW UP INSPECTION REQUIRED
- ☐ NO FOLLOW UP INSPECTION REQUIRED

Findings:

13 Number of Comments

6 Number of Corrective Actions

☒ Corrective Action Response Requested**ANY CORRECTIVE ACTION(S) FROM
PREVIOUS INSPECTIONS THAT HAVE NOT
BEEN ADDRESSED ARE STILL APPLICABLE****Contact Information:**

Contact Name	Phone	Email	Comment
Kane, Alexa		alexkane@gmail.com	principal agent (all inspections)

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
214729	WELL	PR	04/01/2020	GW	067-06333	ARGENTA FEE 17	PR

General Comment:

Site inspection by compliance Supervisor Steve Labowskie on 7/10/23. Bradenhead is accesible. No bradenhead tests submitted via electronic Form 17. NOAV issued for no 2021 bradenhead test. Operator is also required to conduct monthly bradenhead pressure monitoring and keep records per Rule 419.

Record of annual meter calibration is required to be displayed in a conspicuous spot, meter house is loicked, no calibration record is visible.

A domestic tap and off location are present but not registered in COGIS, other operator has also been required to confirm who is supplying gas to domestic tap and register it via Form 44.

The co-operator of the location has also been given corrective actions for deterirate stormwater BMPs and noxious weeds along sides of access road.

A FLIR survey was conducted and no FLIR detectable gas leaks were observed

LocationOverall Good: ☐**Signs/Marker:**

Type	TANK LABELS/PLACARDS		
Comment:			
Corrective Action:		Date:	
Type	WELLHEAD		
Comment:			
Corrective Action:		Date:	

Emergency Contact Number:

Comment:		
Corrective Action:		Date: _____

Good Housekeeping:

Type	WEEDS		
Comment:	noxious weeds on each side of access road, see photo #14 in photo document		
Corrective Action:	Control weeds	Date:	07/25/2023

Overall Good: ☐**Spills:**

Type	Area	Volume		
------	------	--------	--	--

In Containment: No

Comment: ☐ Multiple Spills and Releases?**Equipment:**

			corrective date
Type: Horizontal Heated Separator	# 1		
Comment:	oxide staining becoming excessive, see photo 6		
Corrective Action:		Date:	
Type: Ancillary equipment	# 1		
Comment:	wellhead		
Corrective Action:		Date:	
Type: Other	# 1		
Comment:	domestic tap		
Corrective Action:	confirm which operator is supplying domestic tap, register tap and off location flowline via Form 44. Note: gas used by domestic taps is required to be reported on monthly Form 7.	Date:	07/25/2023
Type: Flow Line	# 2		
Comment:			
Corrective Action:		Date:	
Type: Gas Meter Run	# 1		
Comment:	Meter shed locked, unable to observe calibration record, see photo 11		
Corrective Action:	Post meter calibration (within last year) in conspicuous place	Date:	07/25/2023

Type: Ancillary equipment	# 1	
Comment:	telemetry	
Corrective Action:		Date:
Type: Bradenhead	# 1	
Comment:		
Corrective Action:		Date:
Type: Bird Protectors	# 1	
Comment:		
Corrective Action:		Date:

Tanks and Berms:

Contents	#	Capacity	Type	Tank ID	SE GPS
PRODUCED WATER	1	OTHER	OTHER		37.049369,-107.493029
Comment:	bull plugs missing/no screen over openings. Corrosion and holes noted in topo of tank, see photo 5				
Corrective Action:	Inspoect/repair/paint above ground portions of tank per Rule 609.b				Date: 08/11/2023

Paint

Condition	Inadequate	
Other (Content)		
Other (Capacity)		
Other (Type)		

Berms

Type	Capacity	Permeability (Wall)	Permeability (Base)	Maintenance
Metal	Adequate	Walls Sufficent	Base Sufficent	Adequate
Comment:				
Corrective Action:				Date:

Venting:

Yes/No	NO	
Comment:		
Corrective Action:		Date:

Flaring:

Type	
Comment:	
Corrective Action:	Date:

Inspected FacilitiesFacility ID: 214729 Type: WELL API Number: 067-06333 Status: PR Insp. Status: PR**Producing Well**

Comment:

Corrective Action:

Date:

BradenHeadDate of Last Brhd Test: 11/10/2011Annual Brhd Completed? NoLast Brhd Test Results Initial Surf Csg Pressure: 0 Fluid Type: _____End Surf Csg Pressure: 0

Comment:

bradenhead plumbed above surface with valve and gauge, no Form 17 in COGIS database since 2011. Note: operators are also required to monthly monitor bradenhead pressures and maintain records and notify if bradenhead pressures exceed .3 psi X deptjh of surface casing.

Corrective Action:

Submit annual bradenhead test via electronic Form 17 per Rule 419.c

Date:

Reclamation - Storm Water - Pit

Storm Water:

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment
Compaction	Pass	Compaction				
Gravel	Pass	Gravel				
Ditches	Pass					
Rip Rap	Pass					
Waddles	Fail					deteriorated

Comment: straw wattles on west side of location fill slope are deteriorated to debris, see photo 13

Corrective Action: repair/maintain or remove BMP if no longer needed, per Rule 1002.f and 606

Date: 08/11/2023

Pits: ☒ NO SURFACE INDICATION OF PIT

Optical Gas Imaging SurveySurvey Type: RoutineCurrent Operations: ☒ Production ☐ Workover ☐ Flowback ☐ Referred to APCD

GPS(entrance of location): Lat: _____ Long: _____

Wind: Calm Speed: _____ (mph) Direction From: _____ Weather: _____ Temperature: (F)

Assisting Staff: _____ Camera #: _____

☐ Visible Smoke ☐ Referred to CDPHE

Times Surveyed

Equipment Surveyed

Time Survey Start	AM/PM	Time Survey End	AM/PM

Equipment
Separation Equipment
Flowline
Wellhead(s)

Comment: No FLIR detectable gas observedCorrective
Action:

Date:

Attached DocumentsYou can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
403461105	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6177395
700300650	INSPECTION PHOTOS	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6177394