

State #1 Existing WBD



Details		DEPTH	WELLBORE	DEPTH	Details	
*Cement is Class G 1.15 cu ft/sk yield 15.8# *OH assume 20% cement loss				Surf	Top off cement	
<div><div></div><div></div></div>	Existing Cement New Cement					
8-5/8" Surface Casing: (125 sx cement to surface)		174		224	75sx Cement Plug Surface shoe and surface Isolation (225' plug)	
		1,248				
110sx Cement Plug Upper Pierre and Fox Hills Isolation (300' plug)		1,548				
		</				