

OPERATOR:	<a href="#">Summit Oil &amp; Gas LLC - 10774</a>
WELL:	<a href="#">Fiscus #1</a>
FIELD:	<a href="#">Wildcat - 99999</a>
API #	<a href="#">05-123-14252</a>
LEASE #:	-
UIC #:	-
BASIN:	<a href="#">Denver - Julesburg</a>

CNTY:	<u>Weld</u>	FTG:	<u>660 FNL</u>
STATE:	<u>CO</u>	Q-Q:	<u>NWNW</u>
ROTARY SPUD:	<u>4-Apr-89</u>	SEC.:	<u>14</u>
COMP/PA:	<u>15-Apr-89</u>	TWS:	<u>7N</u>
STATUS:	<u>DA</u>	RGE:	<u>59W</u>
WBD DATE:	<u>3-Aug-23</u>	BY:	<u>SMB</u>
LAT/LONG:	<u>40.580366/-103.951943</u>		

<u>WL</u>	IP GAS:	0
	IP OIL:	0
	IP WTR:	
	CUM GAS:	
	CUM OIL:	
	CUM WTR:	
	LAST PROD:	

## CURRENT WELLBORE DIAGRAM

KBE:	<u>4981</u>	'
KB:	<u>9</u>	'
GLE:	4972	'

WCR 115 &amp; WCR 80. N 1.0. W 1.0. S Into.

### Weld on Plate

### Plug #3

TD (ft): 6900 '  
PBTD (ft): 0 '

CASING HEAD: [None](#)  
WELLHEAD: [None](#)

## CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)	JTS
12 1/4	8 5/8	24		0	235	

### *Float Collar @*

## TUBING RECORD

COND:

DATE:

SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	TALLY (ft)	JTS

8 5/8" 24# Csg @ 235 '  
w/ 165 sxs  
Plug #2

## Plug #2

ITEM	DESC	SIZE (in)	TALLY (ft)	JTS

Top Laramie Shale @	1
Base Laramie Shale @	201
Top Laramie-Fox Hills @	201
Base Laramie-Fox Hills @	531
Top Pierre Shale @	531
Base Pierre Shale @	821
Top Upper Pierre @	821
Base Upper Pierre @	1541
Top Niobrara @	5968
Top Codell @	6250
Top DSND @	6684
Top JSND @	6712

## PERFORATION RECORD

[illegible]

## WELLWORK HISTORY

## DA since 1989

**Hole full of 9.3# mud**

**Plug 1 = 30 sx from 6725' to 6650'**

**Plug 2 = 25 sx at 235' (btm of surf casing)**

**Plug 3 = 5 sx from 10' ot 0'**

**Cut off surface 4' below ground level and weld on plate**

## Plug #1

**TD @ 6900 '**  
**7 7/8" Hole**