





PO Box 329
Ft. Lupton, CO 80621
(303) 654-9202

Well Name				Rig No.		Date		Field Ticket No.			
BOX ELDER-STATE #4-10				ENSIG 122		07/19/23		1646 Page #1			
State		County		API No.		Customer		Lift Pressure & Pop Off			
CO		ARAPAHOE #005		05-005-06549		CIVITAS - JASON GIBBS		Lift:	5000/2900	Pop Off:	4500/2000
Pump	Bulk	Job Type	Last Tckt?	Empl. No.	Employee Name		Water PH:	7	Cmt Type:	G NEAT	
4787	7520	BALANCE	NO	53526	CHRIS SHEETS		CSG Size:	N/A	TBG Size:	DP 4.5	
Job Supervisor:				53308	JAMES WILEY		TBG Dpth:	DP 7514'/3200'	Open Hle:	10"	
EDGAR DIAZ				53480	BLAKE		CSG/ANRL:	717.5/298.6 BBLS	TBG Vol:	DP 106.7/45.4 BBLS	
Remarks:						Well Information					
PLUG (1) 100 SKS G NEAT, 2 GALLON RETARDE, 50# SUGAR PLUG (2) 50 SKS G NEAT, 1 GALLON RETARDE, 50# SUGAR						Description		Depth			
						PLUG 1 TOC		7314'			
						DP		7514'			
						HOLE 10"		7514'			
						PLUG 2 TOC		3100'			
						DP		3200'			
						HOLE 10"		3200'			
Customer Signature:											
Time	Injection		Pressure		Cement Slurry		Remarks				
	RATE	BBLS IN	PSI	WEIGHT	YIELD						
00:01						ARRIVE LOCATION					
00:15						JSA/SPOT/CHECKLIST/RIG UP					
02:05						SAFETY MEETING/JSA WITH RIG CREW					
02:15						PRESSURE TEST 5000 PSI					
02:20	3.7	30	810	8.33	0	BRAKE CIRCULATIOS 30 BBLS H2O					
02:30	4	20.4	700	15.8	1.15	CMT/100 SKS G NEAT 15.8#/VERIFY BY SCALES					
02:37	4	5.5	300	8.33	0	DISPLACE 5.5 BBLS H2O					
02:39						SHOW DOWN					
02:43						TURN OVER TO RIG TO FINISH DISPLACE 98.1 BBLS					
03:00						STAND BY FOR PLUG 2					
06:15						CONNECT TO DP FOR PLUG 2					
06:20						SAFETY MEETING/JSA WITH RIG CREW					
06:25	3.5	30	600	8.33	0	BRAKE CIRCULATION 30 BBLS H2O					
06:35	4	10.2	520	15.8	1.15	CMT/50 SKS G NEAT 15.8#/VERIFY BY SCALES					
06:39	4	5.5	120	8.33	0	DISPLACE 5 BBLS H2O					
06:42						SHOW DOWN					
06:45						TURN OVER TO RIG TO FINISH DISPLACE 38.9					
07:00						STAND BY FOR PLUG 3					
Unit	Desc		QTY	RATE	TOTAL	UNIT	DESC		QTY	RATE	TOTAL
Sub Total:				Surcharge:		Sub Total:					
Customer Approval:						Tckt Total: \$ 0.00					

Box Elder State 04-10
AFE: P1666C
COST CODE: 8306.240
ROUTING: TREVIN
JASON GIBBS
DATE SIGNED:
07-20-23

J. Gibbs

[illegible]



Billie