

Well Name: BOX ELDER FARMS 06-32

API # 0500108328	Surface Legal Location SWSE 6 3S 65W	Field Name	Permit Number	State CO	Well Configuration Type VERTICAL
Ground Elevation (ft) 5,376.00	Casing Flange Elevation (ft)	Orig KB-Ground Distance (ft) 0.00	KB-Casing Flange Distance (ft)	Surface Spud Date 8/25/1984 00:00	Final Rig Release Date

Job: Abandon Well / Abandon Well , 7/5/2023 06:00, 22096

Job Category Abandon	Primary Job Type Abandon Well	Secondary Job Type Abandon Well
-------------------------	----------------------------------	------------------------------------

Start Date 7/5/2023	End Date 7/9/2023
------------------------	----------------------

Objective

SUMMARY

Rpt #	Start Date	End Date	24 Hr Summary	REMARKS/ISSUES
1.0	7/5/2023	7/6/2023	SAFETY MEETING WITH RIG CREW, PREPARE LOCATION TO MIRU, LOCATION TO WET TO MOVE IN, FINISH RIGGING DOWN OFF PREVIOUS LOCATION	
2.0	7/6/2023	7/7/2023	SAFETY MEETING, MIRU, NU KLX BOP'S, TEST BOP WITH WALKER TESTING 250 PSI LOW, 3000 PSI HIGH, 7 1/16" 5K DOUBLE GATE BOP, W/ BLIND RAMS ON BOTTOM AND 2 3/8" PIPE RAMS ON TOP, OFF LOAD 2 3/8" DP, STRAP AND COUNT ALL DP, CHANGE OUT HANDLING TOOLS TO 2 3/8", SPUD WELL, DRILL OUT CMT FROM 300' TO 400', CURRENT DEPTH 439'	
3.0	7/7/2023	7/8/2023	SAFETY MEETING WITH RIG CREW, FUNCTION TEST BOP, CONTINUE TO DRILL THROUGH CMT PLUGS FROM 520'-600', CIRCULATE DRILL PIPE DOWN TO 1800' DILL OUT CIBP, CIRCULATE DP DOWN TO 7500', CIRCULATE HOLE CLEAN, PRESSURE TEST CSG TO 500 PSI, GOOD PRESSURE TEST, LAY DOWN DRILL PIPE TO 6000'	
4.0	7/8/2023	7/9/2023	SAFETY MEETING WITH RIG CREW, FUNCTION TEST BOP, CONTINUE TO LAY DOWN DP, OOH WITH DRILL PIPE, MIRU WL CREW, RIH W/ CIBP AND SET @ 7500', POOH AND RIH W/ DUMP BAILER W/ 2 SKS OF CMT, POOH, RIH W/ RBL TO 4000', POOH, RIH AND SHOOT PERFS @ 3200' & 3000', POOH, RDMO WL CREW, RIH W/ CICR AND SET @ 3175', MIRU CMT CREW, SAFETY MEETING WITH RIG CREW AND CMT CREW, CIRCULATE WELL AND CLEAN WELL, PUMP CIRCULATING SQUEEZE FROM 3200'-2900', 100SKS OF G CMT(20.4BBL), 1.15 YIELD, 5.0 GAL/SK, DISPLACE 6.48BBL, GOOD CIRCULATION THROUGH PERFS, LAY DOWN 12 JTS AND REVERSE CIRCULATE WELL, TOO H TO 1890' PUMP CMT PLUG FROM 1890'-1690', 5BBL H2O, 20SKS OF G CMT(4.1BBL), 1.15 YIELD, 5.0 GAL/SK, DISPLACE 5.3BBL, TOO H TO 1350' PUMP CMT PLUG FROM 1350'-1150', 5 BBL H2O, 20SKS OF G CMT(4.1BBL), 1.15 YIELD, 5.0 GAL/SK, DISPLACE 3.5BBL, TOO H TO 700' PUMP CMT PLUG FROM 700'-0', 5 BBL H2O, 70SKS OF G CMT(14.3BBL), 1.15 YIELD, 5.0 GAL/SK, DISPLACE 0BBL, TOO H TO 700', CMT TO SURFACE W/ TOP OFF	
5.0	7/15/2023	7/15/2023	BOX ELDER FARMS 06-32 WAS CUT AND CAPPED ON 7/15/2023.	