

**FORM
INSP**Rev
X/20**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

08/07/2023

Submitted Date:

08/09/2023

Document Number:

698600895

FIELD INSPECTION FORMLoc ID 336974 Inspector Name: St John, William (Cal) On-Site Inspection ☐ 2A Doc Num: _____**Operator Information:**

OGCC Operator Number: 66190

Name of Operator: OMIMEX PETROLEUM INC

Address: 2501 HARWOOD ST STE 1238

City: DALLAS State: TX Zip: 75201

Status Summary:

- ☒ THIS IS A FOLLOW UP INSPECTION
- ☒ FOLLOW UP INSPECTION REQUIRED
- ☐ NO FOLLOW UP INSPECTION REQUIRED

Findings:

8 Number of Comments

1 Number of Corrective Actions

- ☒ Corrective Action Response Requested

**ANY CORRECTIVE ACTION(S) FROM
PREVIOUS INSPECTIONS THAT HAVE NOT
BEEN ADDRESSED ARE STILL APPLICABLE****Contact Information:**

| Contact Name | Phone | Email | Comment |
|---------------------|-------|----------------------------------|-------------------------|
| McGlaughlin, Dennis | | Dmac@ravenwoodlabs.com | 7/16/2023 |
| Leonard, Mike | | mike.leonard@state.co.us | Compliance Manager |
| Pesicka, Conor | | conor.pesicka@state.co.us | |
| Kirschner, Steven | | steven.kirschner@state.co.us | Enforcement Supervisor |
| Chambers, Kit | | Kchambers@ravenwoodlabs.com | 7/16/2023 |
| Quint, Craig | | craig.quint@state.co.us | E Compliance Supervisor |
| , Engineering | | dnr_cogccengineering@state.co.us | |
| Hickey, Mike | | michael.hickey@state.co.us | |
| Ferrin, Jeremy | | jeremy.ferrin@state.co.us | Enforcement Officer |

Inspected Facilities:

| Facility ID | Type | Status | Status Date | Well Class | API Num | Facility Name | Insp Status |
|-------------|------|--------|-------------|------------|-----------|------------------|-------------|
| 281152 | WELL | PR | 03/04/2007 | GW | 125-09642 | BLEDSE 3-26-5-45 | PR |

General Comment:

Follow up Inspection conducted due findings during previous Routine Inspection completed 08/02/2023 document number 698600868. Routine Inspection conducted as response to Landowner reporting damage to irrigation system pivot arm coming into contact with tubing sticking out of the wellbore. Tubing was forced over by Pivot Arm and split approximately 6" above well cap. Split in tubing is allowing well to continuously vent gas.

Operator has stated that they had someone go out and blow the well down and there is a crew on standby to complete repair work on the well pending access road and weather conditions.

Blowing down the well will have little to no lasting effect on the well venting without pumping a kill fluid or mud down the wellbore to stop the gas flow. Blowing the well down relieves the pressure trapped inside the wellbore at that time. Once the well is shut in the pressure will start to recharge as the well continues to emit gas to the surface. The continued release of gas to the atmosphere is only limited by the well pressure and the restriction of the size of the split in the tubing. The well was venting at the time of the Follow-up Inspection.

LocationOverall Good: ☐

Emergency Contact Number:

Comment:

Corrective Action:

Date: _____

Overall Good: ☐**Spills:**

| | | | | |
|------|------|--------|--|--|
| Type | Area | Volume | | |
|------|------|--------|--|--|

In Containment: No

Comment:

☐ Multiple Spills and Releases?**Venting:**

| | | | |
|--------------------|---|-------|------------|
| Yes/No | YES | | |
| Comment: | <p>Tubing with valve in wellbore appears to of been pushed by gas pressure high enough it came into contact with irrigation system pivot arm and is bent over. Tubing has split at bend and is venting uncontrolled.</p> <p>Follow up Inspection 8/7/2023 - Well is continuing to vent to atmosphere,</p> | | |
| Corrective Action: | <p>Inspect and service the wellhead, tree, and related surface control equipment to comply with Rule 603.c.(14).</p> <p>Follow up Inspection 8/7/2023 - Corrective Action Date remains the same to document noncompliance.</p> | Date: | 08/03/2023 |

Flaring:

| | | |
|--------------------|--|-------|
| Type | | |
| Comment: | | |
| Corrective Action: | | Date: |

| Inspected Facilities | | | | | | | | | |
|----------------------|--------|-------|------|-------------|-----------|---------|----|---------------|----|
| Facility ID: | 281152 | Type: | WELL | API Number: | 125-09642 | Status: | PR | Insp. Status: | PR |

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

| Document Num | Description | URL |
|--------------|-------------------------|---|
| 403491400 | INSPECTION SUBMITTED | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6212890 |
| 698600907 | Inspection Photos | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6212874 |
| 698600908 | 08/07/2023 Tubing Video | http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6212875 |