



00636015

COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS

(Indicate nature of data by checking below)

Locate Well Correctly

- Notice of intention to drill (attach plat) \_\_\_\_\_  
 Notice of intention to change plans \_\_\_\_\_  
 Notice of date for test of water shut-off \_\_\_\_\_  
 Report on result of test of water shut-off \_\_\_\_\_  
 Notice of intention to re-drill or repair well \_\_\_\_\_  
 Notice of intention to clean out well \_\_\_\_\_  
 Statement of shooting \_\_\_\_\_  
 Statement of perforating \_\_\_\_\_  
 Notice to pull or otherwise alter casing \_\_\_\_\_  
 \* Notice of intention to abandon well \_\_\_\_\_  
 Report of work done on well since previous report \_\_\_\_\_

		33	

Notice to do work ☒ Land: Fee and Patented ☒  
 Report of work done ☐ State ☐ Lease No. \_\_\_\_\_

Colorado Baca Interstate Greenwood  
 State County Field

1 Morris SE/4 SE/4 NW/4 33-34S 41W 6th P.M.  
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 2970 Ft. (N) of Section Line and 2310 Ft. (E) of  
~~(S)~~ ~~(W)~~  
 Section Line.


The elevation above sea level is 3578 Ft. D.F.

Details of Plan of Work: (State names of and expected depths to objective sands.  
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing  
 points, and all other important proposed work.)

1. Permission is requested to plug and abandon this drilling well. The following sands were drill stem tested and found to be void of commercial production: Topeka, Lansing, Cherokee, Atoka, Morrow G, and Keyes. Rotary total depth is 4847'.
2. It is planned to spot a 25 sax cement plug at 3600' (top of Cherokee) and 1238' (bottom of 8-5/8 casing). Rotary hole between plugs will be filled w/heavy rotary mud. A 15 sax cement plug will be placed in the top of the hole for a sealer.

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	
FILE	

Approved: MAY 16 1956  
[Signature]  
 Director



Date May 14, 1956  
 Company J. M. Huber Corp.  
 Address Box 831, Borger, Texas  
 By Robert V. Baigler  
 Title Petr. Engineer

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.