



RECEIVED

JUN 29 1972

OIL & GAS COM. DIV.

OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplate	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Nicodemus WELL NO. #1-6

FIELD Flank Cherokee WILDCAT \_\_\_\_\_ COUNTY Baca

LOCATION C/SE/SE Section 6 Township 34S Range 42 Meridian \_\_\_\_\_  
(Quarter Quarter)

660 feet from S Section Line and 660 feet from E Section Line  
N or S E or W

(DETAILS OF WORK)

Ground Level Elev. 3808

This is dual string of csg.  
 Long string- Set 30 sx cement plug 4140 to 2977.  
 Short string- Set 15 sx cement plug 2928 to 2361.  
 Shoot off Long string and Short string @ Approximately 1500'.  
 Note 8 5/8" csg @ 1470'.  
 Set 40 sx cement plug @ 1470'.  
 Set 10 sx cement plug @ surface.  
 Cut off 36" below ground level and weld on cap.

DVR	<input checked="" type="checkbox"/>
FJP	<input checked="" type="checkbox"/>
HHM	<input checked="" type="checkbox"/>
JAM	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED: \_\_\_\_\_ Date JUL 10 1972

Company Horizon Oil & Gas Co. of Texas Date June 27, 1972

Address P.O. Box 7, Spearman, Tex. Phone No. 806-659-2544

By [Signature] Title Production Mgr.  
(Signature)

Director [Signature]