



00594836

REV. 7-84

# ANALYSIS GAS CONSERVATION COMMISSION DEPARTMENT OF NATURAL RESOURCES OF THE STATE OF COLORADO

RECEIVED

OCT 28 1980

File in duplicate for Patented and Federal lands.  
File in triplicate for State lands.

COLO. OIL &amp; GAS CONS. COM. LEASE DESIGNATION AND SERIAL NO.

Cook #7-7

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

N/A

8. FARM OR LEASE NAME

Cook

9. WELL NO.

#7-7

10. FIELD AND POOL, OR WILDCAT

Walsh

11. SEC., T., E., M., OR BLK. AND SURVEY OR AREA

7-33 S-43 W

12. COUNTY

Baca

13. STATE

CO

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1.

OIL WELL ☐ GAS WELL ☒ OTHER Dry hole

2. NAME OF OPERATOR

Michigan Wisconsin Pipe Line Company

3. ADDRESS OF OPERATOR

717-17th Street, Suite 2500, Denver, CO 80202

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.  
See also space 17 below.)  
At surface

At proposed prod. zone

Ctr. SW $\frac{1}{4}$  of Section 7, T. 33 S., R. 43 W.

14. PERMIT NO.

801333 API 05-009-6283.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

16.

### Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

#### NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐PULL OR ALTER CASING ☐FRACTURE TREAT ☐MULTIPLE COMPLETE ☐SHOOT OR ACIDIZE ☐ABANDON ☐REPAIR WELL ☐CHANGE PLANS ☐

(Other)

#### SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐REPAIRING WELL ☐FRACTURE TREATMENT ☐ALTERING CASING ☐SHOOTING OR ACIDIZING ☐ABANDONMENT ☒

(Other)

(NOTE: Report results of multiple completion on Well  
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work 10/24/80

Plugged and abandoned subject well in the following manner:

T.D.-3,200' 9.1 ppg drilling mud  
3,200'-2,900' Cement plug (60 sx)  
2,900'-415' 9.1 ppg drilling mud  
415'-315' Cement plug across show @ 417' (8-5/8, 23# K-55 cemented (25 sx) 417' to surface)  
315'-40' 9.1 ppg drilling mud  
40'-7' Cement plug (10 sx)  
Casing cut-off 3' below G.L. and welded a steel plate on casing.  
Per verbal permission to P&A from Mr. Morrell on 10/20/80.

DVR	
FJP	
HHM	
JAM	
JJD	
RLS	
CGM	

18. I hereby certify that the foregoing is true and correct

SIGNED

Michael W. Nugen

TITLE

Senior Drilling Engineer

DATE

10/27/80

(This space for Federal or State office use)

APPROVED BY

J. Rogers

TITLE

DIRECTOR  
O&G CONS. COM.

DATE

NOV 21 1980

CONDITIONS OF APPROVAL, IF ANY: