



OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Knapp Uranium Development Company Field Wildcat X
 Lease Name Harper Block Well No. 1 County Mesa
 Location NW¹/₄ NW¹/₄ Section 15 Township 2N Range 3W Meridian Ute
 (Quarter Quarter)
913.4 feet from N Section line and 1138.8 feet from W Section Line
 N or S E or W

TOTAL DEPTH 2291 Feet DATE OF PLUGGING May 10, 1958

DETAILS OF WORK

- Set 26 sacks Regular Ideal Cement plug from 2239 to 2291 feet with dump bailer Filled hole to 99' (2140' fill up) 214 bbl (est.) with heavy mud (12# est.) from mud pit.
- Set 14 sacks Regular Ideal Cement plug from 71 to 99 feet with dump bailer Filled hole to 15' with heavy mud as above.
- Set 10 sacks Regular Ideal Cement plug from 15 feet to surface.

Hole clean when cemented,

99' of 10 3/4 inch surface casing left in hole from surface to 99' this casing originally cemented with 48 sacks reg. Ideal Cement

AJJ	
DVR	
WRS	<input checked="" type="checkbox"/>
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: _____ Date MAY 14 1958
 Company Knapp Uranium Development Date May 12, 1958
 Address 555 East 5600 South
Salt Lake City, Utah Phone No. AM 6-3218
 Director A. J. Heroin By Max A. Key Title Geologist
 (Signature)