

OIL AND GAS CONSERVATION COMMISSION

RECEIVED

APR 8 1970

C



00603337

STATE OF COLORADO

COLO. OIL & GAS CONS. COMM.

or Patented and Federal lands.
or State lands.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. Denver 056445-A	
2. NAME OF OPERATOR Alfred M. Buranek		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 525 Atlas Bldg, Salt Lake City, Utah 84101		7. UNIT AGREEMENT NAME Knapp Sundown	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface Well #1, Denver 056445-A, SW SW Sec. 1, T.2N., R.3W., Ute Meridian, Mack Field, Mesa Co., Colorado (658' FSL, 670'FWL) At proposed prod. zone		8. FARM OR LEASE NAME	
14. PERMIT NO.		9. WELL NO. No. 1 Gov't.	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4821' G.L.		10. FIELD AND POOL, OR WILDCAT Mack (510), Morrison	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 1, T.2N., R.3W.	
		12. COUNTY OR PARISH Mesa	13. STATE Colo.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	

SUBSEQUENT REPORT OF:


WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input checked="" type="checkbox"/>
(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work Completed 4-3-70

T.D. 2395' Bled well down and killed with water. Picked up 2" tubing and ran to 2380' depth. Displaced water with 12.7# mud. Spotted 20 sx cement plug @ 2380' depth, top estimated @ 2280' depth in 7" casing. Pulled tubing and welded on pulling nipple. Could not get casing off slips so cut head off surface csg. Tried to cut csg at 1600' & 1100' depth. Cut at 620' approx. and pulled 19 jts. & one piece (623.05') Ran 2" tubing to 675' depth and spotted 30 sx cement plug with base at 675' and top estimated @ 575' depth. Pulled tubing to 120' and set 20 sx cement plug with base at 120' and top at est. 80' depth over base of 10-3/4" surface casing. Intervals between plugs filled with 12.7# gel mud. Cemented in dry hole marker in top with 5 sx. of cement. Pulled out cement unit pad and drug location. Location ready for inspection 4-3-70



Ex Gas Prod.

18. I hereby certify that the foregoing is true and correct

SIGNED

R. Higgins

TITLE

Agent

DATE

4-7-70

(This space for Federal or State office use)

APPROVED BY

W. Rogers

TITLE

DIRECTOR

O & G CONS. COMM.

DATE

APR 9 1970

CONDITIONS OF APPROVAL, IF ANY:

10/13/65

Lee -

Requested form 10
by phone 10/13/65
Let me know when
and if it comes in,

Hack

10/18/65

Bogdanich called and
said they were in the process
of selling well to a Mr.
Buraneck. He will send
new owners address, etc.

Hack