

**FORM  
INSP**Rev  
X/20**State of Colorado  
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

09/19/2023

Submitted Date:

09/21/2023

Document Number:

702501877

**FIELD INSPECTION FORM**Loc ID 313420 Inspector Name: Burchett, Kirby On-Site Inspection ☐ 2A Doc Num: \_\_\_\_\_**Operator Information:**

OGCC Operator Number: 10407

Name of Operator: ANTLER ENERGY LLC

Address: PO BOX 104

City: BAGGS State: WY Zip: 82321

**Status Summary:**☐ THIS IS A FOLLOW UP INSPECTION☒ FOLLOW UP INSPECTION REQUIRED☐ NO FOLLOW UP INSPECTION REQUIRED**Findings:**

20 Number of Comments

14 Number of Corrective Actions

☒ Corrective Action Response Requested**ANY CORRECTIVE ACTION(S) FROM  
PREVIOUS INSPECTIONS THAT HAVE NOT  
BEEN ADDRESSED ARE STILL APPLICABLE****Contact Information:**

Contact Name	Phone	Email	Comment
Evans, Clay	(307) 380-7616	clay@antler-energy.com	

**Inspected Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
223626	WELL	PR	12/01/2021	GW	081-60067	POLE GULCH UNIT 2	PR

**General Comment:****ECMC Inspection Report Summary**

On Tuesday, 09/19/2023, Inspector Kirby Burchett, conducted a routine field inspection at Antler Energy LLC on the Pole Gulch Unit 2 well, Location #313420, in Moffat County, Colorado.

This location is within or in close proximity to a CPW District with High Priority, NSO, Density, and Other Consultation Habitat Regulations.

Any Corrective Actions from previous Inspections are still applicable.

While there the following compliance issues were observed:

1. Debris
2. Weeds
3. Stained soil
4. Unmarked anchors
5. Open end tank valves
6. Equipment open to wildlife
7. No sign at tank battery
8. Insufficient tank labels
9. Stormwater BMPS insufficient
10. Gas calibration not visibly displayed
11. Production tank on unstable ground
12. No pit permit on file for production pit

Refer to Inspection Photos for observed compliance issues.

A follow up on this site inspection will be conducted to ensure all compliance issues have been corrected to comply with ECMC rules.

**Location**Overall Good: ☐

<b>Signs/Marker:</b>			
Type	BATTERY		
Comment:	No sign at tank battery		
Corrective Action:	The Tank battery sign will be no less than 3 square feet and no more than 6 square feet, and will provide: Name of the Operator; Telephone number at which the Operator can be reached at all times; Telephone number for local emergency services (911 where available); The public road used to access the Tank battery site; Well name(s) and API number(s) associated with the Tank battery and the legal location of the Well(s); and Location, including the quarter/quarter section, of the Tank battery.	Date:	10/20/2023
Type	WELLHEAD		
Comment:	Illegible. On the ground		
Corrective Action:	Operators will ensure that signs are well maintained and legible, and will replace damaged or vandalized signs within 30 days of discovery that the sign is no longer legible or is damaged.	Date:	10/20/2023
Type	TANK LABELS/PLACARDS		
Comment:	Production tank labels incomplete		
Corrective Action:	All Tanks and Containers will be labeled pursuant to Rule 605. h. (1). All Tanks with a capacity of 10 Barrels or greater will be labeled or posted with the following information: Name of Operator; Operator's emergency contact telephone number; Tank capacity; Tank contents; and NFPA label or equivalent globally harmonized label.	Date:	10/20/2023
Type	OTHER		
Comment:	Separator units include attached storage tanks. No form of labeling or markers are present to identify a potential hazard or the contents of the storage tank.		
Corrective Action:		Date:	
Type	CONTAINERS		
Comment:	Unmarked chemical tank		
Corrective Action:	Containers that are used to store, treat, or otherwise handle a hazardous material and which are required to be marked, placarded, or labeled in accordance with the U.S. Department of Transportation's Hazardous Materials Regulations, will retain the markings, placards, and labels on the Container. Such markings, placards, and labels will be retained on the Container until it is sufficiently cleaned of residue and purged of vapors to remove any potential hazards.	Date:	09/30/2023

Emergency Contact Number:

Comment: 307-380-7616

Corrective Action:

Date: \_\_\_\_\_

**Good Housekeeping:**

Type	DEBRIS		
Comment:	Random debris		
Corrective Action:	All excess materials, rubbish, supplies, trash, or other waste material will be properly contained until removed from the Oil and Gas Location. At no time will debris be placed or remain on the ground.	Date:	09/30/2023
Type	WEEDS		
Comment:	Oil and Gas Locations will be kept free of all Undesirable Plant Species.		
Corrective Action:	Maintain noxious weed control on all disturbed and reclaimed areas as a result of Oil & Gas activities including access roads.	Date:	09/27/2023

Overall Good: ☐

<b>Spills:</b>				
Type	Area	Volume		
Condensate	Tank	<= 1 bbl		
Comment: Soil stains around tank battery				
Corrective Action: Remove and properly dispose of oily waste and impacted soil.			Date:	10/05/2023

In Containment: No

Comment:

☐ Multiple Spills and Releases?

<b>Fencing/:</b>			
Type	LOCATION		
Comment: Barbed wire. Gate open			
Corrective Action:		Date:	

<b>Equipment:</b>			corrective date
Type: Compressor	# 1		
Comment:			
Corrective Action:		Date:	
Type: Horizontal Heated Separator	# 1		
Comment:			
Corrective Action:		Date:	
Type: Gas Meter Run	# 1		
Comment: Inside separator? Gas meter calibration not visibly displayed.			
Corrective Action: The Operator will conspicuously post and maintain the date of the last meter calibration in a legible condition at each meter at all times.		Date:	09/30/2023
Type: Other	# 1		
Comment: line heater			
Corrective Action:		Date:	
Type: Deadman # & Marked	# 2		
Comment:			
Corrective Action:		Date:	
Type: Bradenhead	# 1		
Comment:			
Corrective Action:		Date:	
Type: Bird Protectors	# 1		
Comment: Compressor exhaust stack lacking wildlife protection			
Corrective Action: All stacks, vents, or other openings will be equipped with screens or other appropriate equipment to prevent entry by wildlife, including birds and bats.		Date:	09/30/2023
Type: Ancillary equipment	# 1		
Comment: Chemical tank inside containment open to wildlife			
Corrective Action: Install or repair wildlife protection equipment.		Date:	09/30/2023

**Tanks and Berms:**

Contents	#	Capacity	Type	Tank ID	SE GPS	
CONDENSATE	1	OTHER	STEEL AST		,	
Comment: Unstable. Leaning into 400 bbl tank stair support.						
Corrective Action:					Date:	

**Paint**

Condition	Adequate	
Other (Content)		
Other (Capacity) 210		
Other (Type)		

**Berms**

Type	Capacity	Permeability (Wall)	Permeability (Base)	Maintenance
Earth	Adequate			
Comment:				
Corrective Action:				Date:

Contents	#	Capacity	Type	Tank ID	SE GPS	
CONDENSATE	1	400 BBLs	STEEL AST		,	
Comment: Open end tank valves						
Corrective Action: All loadlines or tank valves that can be used as a loadline will be capped or plugged.					Date:	09/25/2023

**Paint**

Condition	Adequate	
Other (Content)		
Other (Capacity)		
Other (Type)		

**Berms**

Type	Capacity	Permeability (Wall)	Permeability (Base)	Maintenance
Earth	Adequate			
Comment:				
Corrective Action:				Date:

**Venting:**

Yes/No	NO		
Comment:			
Corrective Action:		Date:	

**Flaring:**

Type		
Comment:		
Corrective Action:		Date:

Inspected Facilities									
Facility ID:	223626	Type:	WELL	API Number:	081-60067	Status:	PR	Insp. Status:	PR
Producing Well									
Comment:	Review of monthly operations records indicate operator is delinquent in submitting monthly operations reports								
Corrective Action:	Submit required Form 7(s) to ECMC						Date:	10/20/2023	

**Reclamation - Storm Water - Pit****Storm Water:**

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment

Comment: Stormwater BMPs need implementation and maintenance.

Corrective Action: Provide proper Stormwater BMPs to control runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation. Vehicle tracking BMPs to control potential sediment discharges from operational roads, well pads, and other unpaved surfaces.

Date: 10/20/2023

**Pits:** ☐ NO SURFACE INDICATION OF PIT

Type: Blowdown

Lined: NO

Pit ID:

Lat:

Long:

Reference Point: \_\_\_\_\_ Other: \_\_\_\_\_ Length: \_\_\_\_\_ Width: \_\_\_\_\_

**Lining:**

Liner Type:

Liner Condition:

Comment:

Corrective Action

Date:

**Fencing:**

Fencing Type:

Fencing Condition:

Comment:

Corrective Action

Date:

**Netting:**

Netting Type:

Netting Condition:

Comment:

Corrective Action

Date:

Anchor Trench Present:

Oil Accumulation:

2+ feet Freeboard:

Comment:

No pit permit on file for production pit.

Corrective Action

Submit an eForm 15 Pit Report to update COGCC records with current information.

Date: 10/05/2023

**Attached Documents**

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
702501879	Inspection Photos	<a href="http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6260068">http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6260068</a>