

RECEIVED
AUG 8 - 1958
(SUBMIT IN TRIPLICATE)

Land Office Denver
Lease No. Colo. 03404
Unit Gilliam Draw



UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY



99999999

103-05250
TICES AND REPORTS ON WELLS

RECEIVED
Conservation Division
Oil & Gas Leasing Branch
GEOLOGICAL SURVEY
MAY 29 1958
Denver, Colorado

NOTICE OF INTENTION TO DRILL.....		SUBSEQUENT REPORT OF WATER SHUT-OFF.....	
NOTICE OF INTENTION TO CHANGE PLANS.....		SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING.....	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF.....		SUBSEQUENT REPORT OF ALTERING CASING.....	
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL.....		SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR.....	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE.....		SUBSEQUENT REPORT OF ABANDONMENT.....	<input checked="" type="checkbox"/>
NOTICE OF INTENTION TO PULL OR ALTER CASING.....		SUPPLEMENTARY WELL HISTORY.....	
NOTICE OF INTENTION TO ABANDON WELL.....			

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

Gilliam Well No. 3 is located 2030 ft. from [N] line and 1930 ft. from [E] line of sec. 36, 19 58

SC SW-NE Sec. 36 (1/4 Sec. and Sec. No.)
Gilliam Draw Unit (Field)

1N (Twp.) 102W (Range) 6 PM (Meridian)

Nio Blanco (County or Subdivision) Colorado (State or Territory)

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

The elevation of the derrick floor above sea level is 5921 ft.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

May 16, 1958 PTD 6149. MI and rig up Well Service Unit, killed well w/mud, started pulling tubing.

May 17, 1958 PTD 0. Well P&A. Finished pulling tubing. Set Baker CI Bridge plug at 6035, dumped 1-1/2 sx cement on plug. Ran Magnatector, indicated 5-1/2" casing froze at 900'. Worked casing 7 hrs pulling 125,000#, worked free to 1280. Cut 5-1/2" csg at 1286 w/McCullough jet cutter, pulled 31 jts - 1306' OAH. Sptd 65 sx cem plug at 1400', WOC 8 hrs, checked plug at 1125', sptd 35 sx cem 690 - 575, sptd 10 sx cem in top surface csg, erected dry hole marker. Job completed at 9:30 P.M.



00065732

I understand that this plan of work must receive approval in writing by the Geological Survey before operation.

Company Phillips Petroleum
Address P. O. Box 2331
Casper, Wyoming

By [Signature]
Title District Superintendent

8-6-58
G. G. Frazier

RECEIVED
GEOLOGICAL SURVEY
MAY 29 1958
DENVER, COLORADO