

OIL AND

GAS

ON COMMISSION  
COLORADO

## PLUGGING RECORD

## INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator W. W. McClure, Trustee 55099 Field - Wildcat X  
 Lease Name Federal D-056382 Well No. 1 County Mesa  
 Location NE SE Section 5 Township 2N Range 2W Meridian Ute  
 (Quarter Quarter)  
2009 feet from S Section line and 831 feet from E Section Line  
 N or S E or W

TOTAL DEPTH 2765 feetDATE OF PLUGGING Aug. 28-Sept. 3, 1959

Verbal OK

## DETAILS OF WORK

- 8-28-59 Set 20 sx cement plug 2% gel from 2630 to 2761  
 8-29-59 Pulled 2431' of 7" casing from hole.  
 Set 25 sx cement plug 2% gel from 2350 to 2430  
 9-1,2-59 Pulled 2100' of 8 5/8 casing from hole; 286' 8 5/8 left  
 in hole. Set 5 sx cement plug from 90 to 105'  
 Left 95' 10 3/4" 28# surface casing in hole.  
 9-3-59 Erected abandonment marker with 2 sx cement plug at top  
 of surface casing; filled sump and mud pits and leveled  
 location with grader. Rig released and hole abandoned.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
JUE	

FILE	
JJD	
FJP	
JAM	
HHM	
WRS	
DVR	
AJJ	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date SEP 17 1959

Director

Company W.W. McClure, Trustee Date Sept. 16, 1959Address Suite 7, 610 Rood Ave. Phone No. CH 2-0113  
Grand Junction, Colo.By Max Krey (Signature) Title Agent

✓