

FORM  
INSPRev  
X/20State of Colorado  
Oil and Gas Conservation Commission1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

08/22/2023

Submitted Date:

09/27/2023

Document Number:

698601018

## FIELD INSPECTION FORM

 Loc ID 337511 Inspector Name: St John, William (Cal) On-Site Inspection  2A Doc Num: \_\_\_\_\_
**Operator Information:**
 OGCC Operator Number: 66190  
 Name of Operator: OMIMEX PETROLEUM INC  
 Address: 2501 HARWOOD ST STE 1238  
 City: DALLAS State: TX Zip: 75201
**Status Summary:**

- THIS IS A FOLLOW UP INSPECTION
- FOLLOW UP INSPECTION REQUIRED
- NO FOLLOW UP INSPECTION REQUIRED

**Findings:**

- 29 Number of Comments
- 14 Number of Corrective Actions
- Corrective Action Response Requested

**ANY CORRECTIVE ACTION(S) FROM PREVIOUS INSPECTIONS THAT HAVE NOT BEEN ADDRESSED ARE STILL APPLICABLE**

**Contact Information:**

Contact Name	Phone	Email	Comment
, Engineering		dnr_cogccengineering@state.co.us	
Ferrin, Jeremy		jeremy.ferrin@state.co.us	Enforcement Officer
Pesicka, Conor		conor.pesicka@state.co.us	
Kirschner, Steven		steven.kirschner@state.co.us	Enforcement Supervisor
Leonard, Mike		mike.leonard@state.co.us	Compliance Manager
Chambers, Kit		Kchambers@ravenwoodlabs.com	
McGlaughlin, Dennis		Dmac@ravenwoodlabs.com	

**Inspected Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
286372	WELL	PR	03/01/2022	GW	125-10291	WALCHLE 5-27-5-43	PR

**General Comment:**

[Routine Inspection.](#)

The name change of the Colorado Oil and Gas Conservation Commission to the Energy & Carbon Management Commission required major server updates and created sync issues for remote field personnel's computers. During this time personnel were not able to complete and uploaded inspections creating a lengthy lag between inspection dates and report submission dates. These circumstances are beyond the Operators control and required dates should be adjusted to match Inspectors FIR submission date. All corrective action dates have been adjusted to accommodate actual FIR submission date. Please contact me directly with any questions or concerns.

Location			
<b>Lease Road:</b>			
Type	Access		
comment:	Two track off maintained county road. Two track has not been maintained.		
Corrective Action:	Repair and maintain lease road to comply with rule 603.l.	Date:	10/28/2023
Overall Good: <input type="checkbox"/>			
<b>Signs/Marker:</b>			
Type	WELLHEAD		
Comment:	Well sign located on meter shed door inside well fencing.		
Corrective Action:		Date:	
Type	TANK LABELS/PLACARDS		
Comment:	No Quantity/Contents/Hazard Placard on tank at Pig Station.		
Corrective Action:	Install sign to comply with Rule 605.h.	Date:	10/28/2023
Emergency Contact Number:			
Comment:	Emergency contact #877-425-4882 posted on well sign is invalid and appears to be disconnected or no longer in service.		
Corrective Action:	Install sign to comply with Rule 605.a.	Date:	10/28/2023
<b>Good Housekeeping:</b>			
Type	UNUSED EQUIPMENT		
Comment:	Production related equipment left inside wellhead fencing.		
Corrective Action:	Comply with Rule 606.	Date:	10/13/2023
Type	WEEDS		
Comment:	Well location has vegetation growing inside fencing. Pig Station has vegetation growing inside fencing.		
Corrective Action:	Comply with Rule 606.	Date:	10/05/2023
Type	DEBRIS		
Comment:	Production related debris left inside wellhead fencing.		
Corrective Action:	Comply with Rule 606.	Date:	10/05/2023
Overall Good: <input type="checkbox"/>			
<b>Spills:</b>			
Type	Area	Volume	
In Containment: No			
Comment:			
<input type="checkbox"/> Multiple Spills and Releases?			
<b>Fencing/:</b>			
Type	WELLHEAD		
Comment:	Stock Panel Fencing		
Corrective Action:		Date:	
Type	LOCATION		
Comment:	Post and Wire Fencing.		
Corrective Action:		Date:	

Type	OTHER		
Comment:	Pig Station - Stock Panel Fencing		
Corrective Action:		Date:	
<b>Equipment:</b>			corrective date
Type: Ancillary equipment	# 1		
Comment:	Pump Jack Power and Control Panel.		
Corrective Action:		Date:	
Type: Vertical Separator	# 1		
Comment:	Inside Metal Meter Shed.		
Corrective Action:		Date:	
Type: Other	# 1		
Comment:	Pump Jack Cement Pad. Pump Jack has been removed but cement pad is still inside fencing.		
Corrective Action:	Comply with Rule 606.	Date:	10/28/2023
Type: Deadman # & Marked	# 2		
Comment:	Located 2 Deadmen. Both markers down. Unable to locate remaining 2 Deadmen.		
Corrective Action:	Install proper guy line markers per Rule 603.j	Date:	10/12/2023
Type: Ancillary equipment	# 1		
Comment:	Wellhead. Well appears to be producing out of casing string. Casing valve closed. Casing is leaking at collar and bad valve on the inlet to meter shed/separator.		
Corrective Action:	Inspect and service the wellhead, tree, and related surface control equipment to comply with Rule 603.c.(14).	Date:	09/29/2023
Type: Other	# 1		
Comment:	Metal Meter Shed.		
Corrective Action:		Date:	
Type: Pump Jack	# 0		
Comment:	Removed.		
Corrective Action:		Date:	
Type: Gas Meter Run	# 1		
Comment:	Gas Meter Run. Chart in Meter Box dated 11-30-22. No Meter Calibration/Test Log. Well Inlet Valve appears possibly closed (Bad Valve). Gas Outlet Valve open. Water Outlet valve closed.		
Corrective Action:	Calibrate gas metering equipment annually to comply with rule 430.d.(1).	Date:	10/28/2023
Type: Prime Mover	# 0		
Comment:	Removed.		
Corrective Action:		Date:	
Type: Pig Station	# 1		
Comment:			
Corrective Action:		Date:	
Type: Bradenhead	# 0		
Comment:	Bradenhead inaccessible or not visible.		
Corrective Action:	Install appropriate fittings to allow bradenhead visual inspection as per Rule 419.a.(1), (2).	Date:	10/08/2023

**Tanks and Berms:**

Contents	#	Capacity	Type	Tank ID	SE GPS
	1		PLASTIC AST		
Comment:					
Corrective Action:					Date:

**Paint**

Condition	
Other (Content)	Not Identified.
Other (Capacity)	Not Marked.
Other (Type)	

**Berms**

Type	Capacity	Permeability (Wall)	Permeability (Base)	Maintenance
Other	Adequate	Walls Sufficient	Base Sufficient	Inadequate
Comment: No netting on open top containment tank.				
Corrective Action: Install or repair wildlife protection equipment.				Date: 10/03/2023

**Venting:**

Yes/No	YES
Comment: Wellhead is leaking gas at collar and reducer.	
Corrective Action:	Inspect and service the wellhead, tree, and related surface control equipment to comply with Rule 603.c.(14). Date: 09/29/2023

**Flaring:**

Type	
Comment:	
Corrective Action:	Date:

**Inspected Facilities**

Facility ID: 286372 Type: WELL API Number: 125-10291 Status: PR Insp. Status: PR

**Idle Well**

Purpose:  Shut In  Temporarily Abandoned Reminder: \_\_\_\_\_

Comment: Pump Jack removed. Rods and tubing have been removed from the wellbore. Casing valve closed. Gas Meter Run Valves: Well inlet valve appears to be closed (Bad Valve), Gas outlet valve open, Water outlet valve closed. Wellhead is leaking at the collar and reducer.

Electronic Well File reflects last Production/Status reported 8/1/2022 and Well Status as PR. Based on current valve settings at the wellhead the well is SI.

Review of monthly operations records indicate operator is delinquent in submitting monthly operations reports.

Corrective Action: **Submit required Form 7(s) to COGCC per rule 413.**

Date: 10/28/2023

**Reclamation - Storm Water - Pit**

**Storm Water:**

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment

Comment:

Corrective Action:

Date: \_\_\_\_\_

**Pits:**     NO SURFACE INDICATION OF PIT

**COGCC Comments**

Comment	User	Date
The name change of the Colorado Oil and Gas Conservation Commission to the Energy & Carbon Management Commission required major server updates and created sync issues for remote field personnel's computers. During this time personnel were not able to complete and uploaded inspections creating a lengthy lag between inspection dates and report submission dates. These circumstances are beyond the Operators control and required dates should be adjusted to match Inspectors FIR submission date. All corrective action dates have been adjusted to accommodate actual FIR submission date. Please contact me directly with any questions or concerns.	stjohnw	09/27/2023

**Attached Documents**

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
698601080	Inspection Photos.	<a href="http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6266565">http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6266565</a>
698601081	Wellhead Collar Video.	<a href="http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6266566">http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6266566</a>