

STATE OF COLORADO  
GAS CONSERVATION COMMISSION  
DEPARTMENT OF NATURAL RESOURCES  
SUBMIT ORIGINAL AND 1 COPY



PA



FOR OFFICE USE ONLY  
ET: [ ] IFE: [ ] LUC: [ ] LSE: [ ]

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

5. FEDERAL INDIAN OR STATE LEASE NO.

6. PERMIT NO. 69 404 ✓

7. API NO. 05 017 6056 ✓

8. WELL NAME Lowe

9. WELL NUMBER 4-X

10. FIELD OR WILDCAT Golden Spike

11. QTR., QTR. SEC., T.E. AND MERIDIAN C NE SW 12-16S045W ✓

OIL WELL  GAS WELL  COALBED METHANE  INJECTION WELL  OTHER

2. NAME OF OPERATOR Murfin Drilling Co., Inc.

3. ADDRESS OF OPERATOR 250 N. Water, Suite 300

CITY STATE ZIP CODE  
Wichita KS 67202

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.  
See also space 17 below.)  
At surface: C NE SW 150' NW of NESW  
At proposed prod. zone: Cheyenne

Check Appropriate Box To Indicate Nature of Notice, Report or Notification

- 13A. NOTICE OF INTENTION TO:
  - PLUG AND ABANDON
  - MULTIPLE COMPLETION
  - COMMINGLE ZONES
  - FRACTURE TREAT
  - REPAIR WELL
  - OTHER \_\_\_\_\_

- 13B. SUBSEQUENT REPORT OF:
  - FINAL PLUG AND ABANDONMENT (SUBMIT 3RD PARTY CEMENT VERIFICATION AND JOB LOG)
  - ABANDONED LOCATION (WELL NEVER DRILLED - SITE MUST BE RESTORED WITHIN 6 MONTHS)
  - REPAIRED WELL
  - OTHER \_\_\_\_\_

\*Use Form 5 - Well Completion or Abandonment Report for subsequent reports of Multiple Completions, Cements and Re-completions

- 13C. NOTIFICATION OF:
  - SHUT-IN/TEMPORARILY ABANDONED (DATE \_\_\_\_\_) (REQUIRED EVERY 6 MONTHS)
  - PRODUCTION RESUMED (DATE \_\_\_\_\_)
  - LOCATION CHANGE (SUBMIT NEW PLAT)
  - WELL NAME CHANGE
  - OTHER \_\_\_\_\_

14. DESCRIBE PROPOSED OR COMPLETED OPERATIONS ON THIS FORM (Include all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give north-south and east-west bearings and measured and true vertical depths for all markers and zones pertinent

15. DATE OF WORK 6/8 - 6/9/94

Sanded bottom @ 5378' & cemented w/5 sx. Shot @ 2409', worked pipe. Shot @ 2226', worked pipe. Left on tension, swedged in overnight. Worked pipe, shot @ 1900', worked pipe. Came loose, pulled sub & 4 jts. Spotted 50 sx cement @ 1900'. Pulled pipe to 1500', spotted 40 sx cement. Pulled pipe to 600', spotted 70 sx. Pulled rest of pipe, mixed 80 sx cement & circulated to surface. 60/40 Poz, 10% gel. JC 6/9/94.

RECEIVED

JUL 8 - 1994

16. I hereby certify that the foregoing is true and correct.

SIGNED By: Kerran Redington TELEPHONE NO. 316-267-3241  
NAME (PRINT) Kerran Redington TITLE Engineering Technician DATE 7/6/94

(This space for Federal or State office use)

APPROVED [Signature] TITLE Engineer DATE 7-14-94  
CONDITIONS OF APPROVAL, IF ANY:



# Kelso Casing Pulling, Inc.

-- INVOICE --

Post Office Box 347  
CHASE, KANSAS 67524  
Phone (316) 938-2943

6953

USED FOR *PIA*  
APPROVED *SI*

(Control# 106292)

BILL TO  
Murfin Drilling Company  
Suite 3000  
250 N. Water  
Wichita, Ks., 67202

SHIP TO  
Murfin Drilling Company  
Suite 3000  
250 N. Water  
Wichita, Ks., 67202

TERMS: NET 30 DAYS. Service Charge of 1½% per month (18% per year) will be added to past due invoices.

ACCOUNT NO.	SALES #	ORDER NO.	SHIP VIA	COLL. PPD.	DATE SHIPPED	TERMS	INVOICE DATE	PAGE
MU672		Lowe #4X	Cheyenne, CO		06/16/94	Net 30	06/16/94	

QUANTITY	ITEM NO.	DESCRIPTION	UNIT PRICE	EXTENDED PRICE
0	1	Move in charge	900.00 0	900.00
0	1923.95	5 1/2" casing	0.60 0	1154.37
0	5	Cement	8.50 0	42.50
0	1	Sand	20.00 0	20.00
0	3	Shots	100.00 0	300.00
0	1	Cutting torch - cut off shot joint	35.00 0	35.00
0	1	Expense for 2 men	80.00 0	80.00
<p>6-8-94 Moved in on location, rigged up pole, checked hole, sanded bottom @ 5378', loaded hole, tore down head. Found 2 big holes in pipe, had welder come out to cut head &amp; surface off &amp; cut 5 1/2 down to good pipe. Put on slip collar, set up floor, cemented bottom w/5 sks. Shot @ 2409', worked pipe for 30 min. Shot @ 2226', worked pipe, left on tension, swedged in overnight.</p> <p>6-9-94 Worked pipe, shot @ 1900', worked pipe for 1 hr. Came loose &amp; pulled sub &amp; 4 joints. Spotted 50 sks cement @ 1900'. Pulled pipe to 1500', spotted 40 sks cement. Pulled pipe to 600', spotted 70 sks cement. Pulled rest of pipe, mixed 80 sks cement &amp; circulated to surface. 60/40 poz 10% gel. Plugging complete.</p>				

\*\*\* ~~XXXXXX~~  ~~XXXXXX~~ \*\*\*

SALE AMOUNT	2531.87
SALES TAX FREIGHT	144.66
<b>TOTAL INVOICE</b>	<b>2676.53</b>

KCC COMMON CARRIER  
ICC MC-115378

DARRELL KELSO - President  
MIKE KELSO - Vice-President

Well, KS  
8861, Great Bend, KS

Phone 913-625-5516, Hays, KS  
Phone 913-672-3471, Oakley, KS

Phone 316-886-5926, Medicine Lodge, KS  
Phone 913-798-3843, Ness City, KS

# ALLIED CEMENTING CO., INC.

7655

Home Office P. O. Box 31

Russell, Kansas 67665

*OID*

Date	6-9-94	Sec.	12	Twp.	16	Range	45	Called Out		On Location	3:00 PM	Job Start		Finish	7:00 PM	
Lease	Lowc	Well No.	4X	Location	Cheyenne Wells 1/4-85-			County	Cheyenne	State	Colo					
Contractor	Kelso Casing Pullers											Owner	Same 2 1/2 W-15			
Type Job	OID Hole Plus											To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.				
Hole Size												T.D.				
Csg.	5 1/2											Depth				
Tbg. Size												Depth				
Drill Pipe												Depth				
Tool												Depth				
Cement Left in Csg.												Shoe Joint				
Press Max.												Minimum				
Meas Line												Displace				
Perf.																

Charge To MurFin Drly Co.  
Street 250 N Water, St. #300  
City Wichita State Kan 67202  
The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No. \_\_\_\_\_  
X [Signature]  
used 240 SKS CEMENT

**EQUIPMENT**

No.	Cementer	Walt Terry
Pumptrk 300	Helper	
No.	Cementer	Wayne
Pumptrk	Helper	
	Driver	
Bulktrk 218	Driver	

Amount Ordered	250 SKS 60/40 per 10% Gel		
Consisting of			
Common	144	SKS @ 6.55	986.40
Poz. Mix	96	SKS @ 3.00	288.00
Gel.	21	SKS @ 9.00	189.00
Chloride			
Quickset			

**DEPTH of Job**

Reference:	Pumptruck	410.00
	2.25 per mile	175.50
	Sub Total	
	Tax	
	Total	585.50

Handling	1.00 per SK	250.00
Mileage	4.0 per SK/mile 78 miles	780.00
	Sub Total	2,493.40
	Total	

Remarks: mixed 50 SKS cement @ 1900', down 5 1/2 casing,  
mixed 40 SKS cement @ 1550' down 5 1/2 casing  
mixed 20 SKS @ 600' down 5 1/2 casing

Floating Equipment  
mixed 80 SKS cement to Circ. to Surface  
**RECEIVED**  
JUL 8 - 1994  
[Signature]