



**MINERAL OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO**

File in duplicate for Patented and Federal lands.  
File in triplicate for State lands.

**RECEIVED**

OCT 17 1969

COLO.

5. LEASE DESIGNATION AND SERIAL NO.  
**OIL & GAS CONS. COMM.**

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/>		7. UNIT AGREEMENT NAME	
2. NAME OF OPERATOR <b>Plains Exploration Company - Union Pacific RR - Petroleum Inc.</b>		8. FARM OR LEASE NAME <b>Baughman "D"</b>	
3. ADDRESS OF OPERATOR <b>1135 Petroleum Club Bldg., Denver, Colo. 80202</b>		9. WELL NO. <b>1</b>	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface <b>CNE NE</b>  At proposed prod. zone <b>Mississippian</b>		10. FIELD AND POOL, OR WILDCAT <b>Wildcat</b>	
14. PERMIT NO. <b>69 463</b>		15. ELEVATIONS (Show whether DF, RT, GR, etc.) <b>4116' GR</b>	
		11. SEC., T., B., M., OR BLK. AND SURVEY OR AREA <b>Sec. 8-17S-45W</b>	12. COUNTY OR PARISH <b>Kiowa</b>
			13. STATE <b>Colorado</b>

16. **Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data**

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input checked="" type="checkbox"/>
(Other) <u>Abandonment</u>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The well was plugged August 30, 1969, by filling it with heavy mud from the total depth to the bottom of the surface pipe.(5421-259). A 15-sack cement plug was set in the bottom 45' of the surface pipe (259-214), then the casing was filled with heavy mud to within 30' of the top. A 10-sack cement plug was set in the top 30' of the surface pipe (42-12).

All measurements are taken from the Kelly bushing which was approximately 10' above the ground.

DVR	<input type="checkbox"/>
FJP	<input checked="" type="checkbox"/>
HHM	<input checked="" type="checkbox"/>
JAM	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>

18. I hereby certify that the foregoing is true and correct

SIGNED Richard W. Volk TITLE Vice President DATE Oct. 16, 1969

(This space for Federal or State office use)

APPROVED BY [Signature] TITLE DIRECTOR DATE OCT 20 1969

CONDITIONS OF APPROVAL, IF ANY: