



DRILLERS LOG

Tallman #1

LOCATION: NW/4 NW/4  
SECTION: 36-168-45W  
Cheyenne County, Colorado  
OPERATOR: International Nuclear Corp.  
CONTRACTOR: L & F Drilling, Inc.

CORE: 1-2-69  
COMP: 1-22-69  
CASING: 8-5/8" @ 271'  
5-1/2" @ 5699'  
T.D. 5700'


0	255	Sand & Shale	Set 8-5/8" casing @ 271' w/ 200 sacks
255	775	Shale	cement, 3% HA5
775	2049	Shale & Anhydrite	
2049	2315	Shale, Anhydrite & Red Bed	
2315	2842	Red Bed & Anhydrite	
2842	3058	Red Bed, Shale & Anhydrite	
3058	3085	Anhydrite & Shale	
3085	3278	Anhydrite, Red Bed & Pyrite	
3278	3455	Anhydrite & Red Bed	
3455	3593	Red Bed & Anhydrite	
3593	3688	Red Bed, Anhydrite & Lime	
3688	3815	Lime & Shale	
3815	3860	Red Bed & Anhydrite	
3860	3894	Lime	
3894	4138	Lime & Shale	
4138	4189	Lime	
4189	4550	Lime & Shale	
4550	4626	Lime, Shale & Chalk	
4626	4970	Lime & Shale	
4970	5041	Lime	
5041	5073	Lime, Shale & Sand	
5073	5213	Lime & Shale	
5213	5265	Shale & Lime	
5265	5376	Lime & Shale	
5376	5421	Lime, Shale & Chert	
5421	5450	Lime	
5450	5513	Lime & Shale	
5513	5543	Lime, Shale & Chert	
5543	5557	Lime & Shale	
5557	5601	Shale & Lime	Set 5-1/2" casing @ 5699'
5601	5700	Lime & Chert	
5700		T. D.	

I certify that this is the true and correct copy of the above log to the best of my knowledge.

BY   
Kenneth G. Fischer  
Vice President

Subscribed and sworn to before me this 24th day of January, 1969.

My commission expires July 28, 1970.

BY   
Virginia A. Fagan  
Notary Public