

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

JUL 19 1966

OIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD



INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Plains Exploration Company Field Wildcat XX
 Lease Name H. Bernerd Fink Well No. 1 County Kiowa
 Location C NW NW Section 4 Township 17 South Range 45 West Meridian 6th P.M.
 (Quarter Quarter)
660 feet from North Section line and 660 feet from West Section Line
N or S E or W

TOTAL DEPTH 5521'DATE OF PLUGGING July 17, 1966

DETAILS OF WORK

The well was plugged July 17, 1966 by filling it with heavy mud from the total depth to the bottom of the surface pipe (5521-215). A 15-sack cement plug was set in the bottom 45 feet of the surface pipe 215-170, then the casing was filled with heavy mud to within 20 feet of the top. A 10-sack cement plug was set in the top 20 feet of the surface pipe (32-12).

All measurements are taken from the Kelly bushing which was approximately 10 feet above the ground.

DVR	
WRS	
HHM	
JAM	
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUL 19 1966

Director

Company Plains Exploration Company Date July 18, 1966
1135 Petroleum Club Bldg.Address Denver, Colorado 80202 Phone No. 266-3163

By

(Signature)
Robert E. JohnsonTitle Vice President