

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED

JUN 28 1967

COLO. OIL & GAS CONS. COMM.



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Plains Exploration Company Field Wildeat xx
 Lease Name H. Bernerd Fink Well No. 1 County Kiowa
 Location C NW NW Section 4 Township 17 South Range 45 West Meridian 6th P.M.
 (Quarter Quarter)
660 feet from North Section line and 660 feet from West Section Line
 N or S E or W

TOTAL DEPTH 5521 DATE OF PLUGGING June 19, 1967 ✓

DETAILS OF WORK

The well was plugged June 13, 1967 by filling to 5050 with coarse sand, then dumping 5 sacks of cement with a bailer. The oil string was pulled and on June 19 a 15 sack cement plug was set in the bottom 45' of the surface pipe 215-170, then the casing was filled with heavy mud to within 20' of the top. A 10-sack cement plug was set in the top 20' of the surface pipe.

DVR	✓
FJP	✓
HHM	
JAM	
JJD	✓

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUN 29 1967

Director

W. RogersCompany Plains Exploration Company Date June 27, 19671135 Petroleum Club Bldg.Address Denver, Colorado 80202 Phone No. 266-3163By Richard W. Volk Title Petroleum Engr.(Signature)
Richard W. Volk*after re-entry*