



OIL AND GAS CONSERVATION COMMISSION
 DEPARTMENT OF NATURAL RESOURCES
 OF THE STATE OF COLORADO

RECEIVED
 OCT 29 1974

File in duplicate for Patented and Federal lands.
 File in triplicate for State lands.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
 Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> <u>WATER INJECTION WELL</u>		5. LEASE DESIGNATION AND SERIAL NO. <u>PATENTED</u>
2. NAME OF OPERATOR <u>CHEVRON OIL CO, WESTERN DIVISION</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR <u>RANGELY, COLORADO 81648</u>		7. UNIT AGREEMENT NAME <u>RANGELY WEBER SAND</u>
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface <u>2996' NSL, 2663' EWL OF SEC. 1, T1N, R102W, 6th P.M.</u> At proposed prod. zone		8. FARM OR LEASE NAME <u>CHASE UNIT</u>
14. PERMIT NO.	15. ELEVATIONS (Show whether DF, RT, GR, etc.) <u>RDB - 5302</u>	9. WELL NO. <u>1</u>
16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data		10. FIELD AND POOL, OR WILDCAT <u>RANGELY WEBER SAND</u>
NOTICE OF INTENTION TO: TEST WATER SHUT-OFF <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> MULTIPLE COMPLETE <input type="checkbox"/> SHOOT OR ACIDIZE <input type="checkbox"/> ABANDON <input type="checkbox"/> REPAIR WELL <input type="checkbox"/> CHANGE PLANS <input type="checkbox"/> (Other) <input type="checkbox"/>		11. SEC., T., R., E., W., OR BLE. AND SURVEY OR AREA <u>SEC. 1 T1N, R102W</u>
		12. COUNTY <u>RIO BLANCO</u>
		13. STATE <u>COLO</u>

DVR	<input checked="" type="checkbox"/>
FJP	<input checked="" type="checkbox"/>
JAM	<input checked="" type="checkbox"/>
JAM	<input checked="" type="checkbox"/>
JJB	<input checked="" type="checkbox"/>
GCH	<input type="checkbox"/>
CGM	<input type="checkbox"/>

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work 9-26-74 to 10-17-74
 SUBJECT WELL WAS PLUGGED AND ABANDONED AS FOLLOWS:
 1. MIR $\frac{3}{4}$ RIGGED UP, PULLED TUBING.
 2. RAN CASING SCRAPER TO 6000'. PUMPED 100 BBLs WATER DOWN 7".
 3. PUMPED 30 SACKS CEMENT BELOW RETAINER SET AT 5900' (5900 TO 6050) AND 4 SACKS CEMENT ABOVE RETAINER (5880 TO 5900).
 4. CIRCULATED WITH 1 BBL CORROSION INHIBITOR MIXED W/WATER.
 5. PUMPED 20 BBLs MUD $\frac{3}{4}$ 150 SACKS CEMENT DOWN 7" SURFACE ANNULUS.
 6. SPOTTED 6 SACKS CEMENT IN TOP OF 7" CASING. (30')
 7. WELDED ON P $\frac{3}{4}$ A MARKER.
 8. COVERED UP CONCRETE AND LEVELED LOCATION.
 9. SEEDED WITH 4# OF 30% ORCHARD GRASS, 25% SMOOTH BROOME, 20% ALTA FESCUE AND 25% PEA RYE.

EXHAUSTED
 OIL WELL

18. I hereby certify that the foregoing is true and correct

SIGNED J.A. THOMPSON TITLE UNIT SUPT. DATE 10-24-74

(This space for Federal or State office use)

APPROVED BY [Signature] TITLE DIRECTOR DATE NOV 1 1974

CONDITIONS OF APPROVAL, IF ANY:

4

X