

OFFICE OF STATE OIL INSPECTOR  
 SUNDRY NOTICES AND REPORTS OF WELLS  
 LOCATED ON PRIVATE LANDS

A-23  
 OFFICE COPY

CHASE UNIT

(Indicate nature of data by checking below)



- Notice of intention to drill.....
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well.....
- Report of work done on well since previous report.....
- " " Setting and cementing 7" casing..... XX

June 22 19 48

Following is a ~~(NOTICE OF INTENTION TO DO WORK)~~ (On land)  
 (report of work done ) ~~(reported)~~ described as follows:

Colorado	Rio Blanco	Rangely
State	County	Field
1	1	1N 102W 6th
(Well No.)	(Lease)	(Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)
The Well is located 2996 ft. (N) of South and 2663 ft. (E) of West		
Line of Sec. 1 <del>(SXX)</del> <del>(WXX)</del>		

The elevation above <sup>RDB</sup> sea level is 5302 ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

On June 18, 1948 ran 395' 23# N-80, 1721' 23# J-55 and 3940' 20# J-55 7" casing set into top of Weber at 6026. Cemented with 1000 sax Monolith Cement and 125# Flocele. WOC 48 hours. Tested casing with 1000# Pressure for 30 minutes. Held Okay.

Approved: June 24 1948  
John E. Brown  
 State Oil Inspector

Company Stanolind Oil and Gas Company  
 Address Rangely, Colorado  
 By J. O. Fair  
 Title Field Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate.