

COLORADO GAS CONSERVATION COMMISSION

No.

Well Log Record

Rio Blanco County
Rangely Field

Casing Record
Size Feet

13-3/8 125
13-3/8 407
7 3958
7 1963

Company Stanolind Oil and Gas Co.
Rangely, Colo.

Lease Associated "B" Lease Well No. 3
Location NE 1/4 SW 1/4 Sec. 3 Twp. 1N Rge 102W

Commenced 3/16/48 Completed 5/10/48
Elevation Tools used C Rotary
Initial Prod. 130 bbls. Bbls Oil
Bbls Water Cu. Ft. Gas
Log Furnished By Stanolind Oil and Gas Co.

Remarks:

Bottom	Total Feet	Formation	Bottom	Formation
0-147	147	Sand, Shale & Boulders		
247	100	Sand and Shale		
470	223	Shale		
550	80	Shale and Sand		
1608	1058	Shale		
1698	90	Sand and Shale		
1929	231	Shale		
2044	115	Shale and sand		
2271	27	Shale		
2353	82	Shale and sand		
2474	121	Shale		
2480	6	Shale and sand		
2602	122	Shale		
2661	59	Shale and sand		
2796	135	Shale		
2843	47	Shale and sand		
2895	52	Shale		
2931	36	Shale and Lime		
3000	69	Shale, Sand & Lime		
3380	380	Sand and Shale		
3400	20	Sand		
3436	36	Lime and sand		
3445	9	Lime, Sand & Shale		
3487	42	Sand & Shale		
3509	22	Lime and Sand		
3535	26	Shale, Sand & Lime		
3563	28	Sandy Shale		
3585	22	Lime and Sand		
3594	9	Lime, sand and shale		
3647	53	Shale and sand		
3653	6	Lime and sand		
3662	9	Sand and shale		
3672	10	Sand		
4317	645	Sand and Shale		
4398	82	Sand		
4438	40	Sand and shale		
4541	103	Sand		
4871	330	Sand and shale		
4908	37	Sand		
5042	134	Sand and shale		
5060	18	Red Beds		
5346	286	Sand and shale		
5647	301	Red Beds		
5683	36	Sand and shale		



From Total Feet Formation

5877 194 Red Beds
5884 4 Sand
5893 9 Red Beds
5904 9 Sand and shale
6270 266 Weber Sand

All formations taken from Drilling Reports

Weber sand cored from 5908 to 6270 using diamonds and Oil Base Mud.
Complete Core Analysis handled by Core Laboratories Inc.

Special Surveys:

Temperature Survey to determine top of cement behind 7" casing. Top of cement behind casing 3100'.

One run Schlumberger Electrical Survey from 542 to 5904.

Schlumberger formation tops:

Dakota	3418	Entrada	4250	Chinle	5014
Morrison	3484	Carmel	4388	Shinarump	5163
Curtis	4144	Navajo	4436	Moenkopi	5227
				Weber	5873 (-678)

Permanent Bench Mark.

Elevation of 7" landing flange 5181.8

Production after shot 8-4-48 70 BO 24 hours 1% BS&W