

OFFICE OF STATE OIL INSPECTOR
 SUNDRY NOTICES AND REPORTS OF WELLS
 LOCATED ON PRIVATE LANDS
 Associated "B" Lease

45
OFFICE COPY



(Indicate nature of data by checking below)

- Notice of intention to drill..... XX
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water-shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well.....
- Report of work done on well since previous report.....

March 12 19 48

Following is a (notice of intention to do work) (On land)
~~(report of work done)~~ (patented) described as follows:

Colorado	Rio Blanco	Rangely
State	County	Field
Well No. 3 NE SW	Sec. 3 T1N	R102W
(1/4 Sec.)	(Twp.)	(Range)
		6th
		(Meridian)

The Well is located 1645' ft. (N) of South and 1460' ft. (E) of West
 Line of Sec. 3 ~~(S)~~ ~~(W)~~

The elevation above sea level isft. (To be determined)

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Drill well to test Weber to an Approximate total depth of 6300'. Set approximately 100' of 13 3/8" 48# 8RT and 400' of 13 3/8" Armco surface casing and circulate cement set approximately 6000' of 7" casing in top of Weber Sand and cement with approximately 1000 sax regular cement. Run temperature survey to locate top of cement behind 7" casing. Produce thru 2 1/2" EUE tubing from open hole 6000' to 6300'. Shoot with S. N. G. as and if required.

Approved: March 15 1948
John E. Brown
 State Oil Inspector

Company Stanolind Oil and Gas Company
 Address.....
 By A. D. Jari
 Title Ass't. Field Superintendent