



COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

132

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well yx _____
 Report of work done on well since previous report _____

Following is a (notice of intention to do work) November 14, 19 52
 (report of work done) (On land) (patented) described as follows:

Colorado Rio Blanco Rangely
 State County Field

5 SH M. E. Hefley 2NW NE 1N 102W 6th
 (Well No.) (Lease) (Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 485 ft. (NW) of North Line and 2370 ft. (E) of East
Line (S) (W)

The elevation above sea level is _____ ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

Well was completed with cable tools to a total depth of 1612 feet on January 27, 1952.
 21 feet of 9 5/8" 36# H-40 surface casing was set. Well was produced from 1607 feet
 with a potential test of 43 BOPD. Total gross accumulative production as of 11/1/52
 was 115 bbls. Well has ceased to produce in commercial quantities and will be
 abandoned as follows:

1. 25 sax plug set - 1612 - 1587.
2. Hole filled with mud.
3. Surface marker set with 5' cement plug.

Approved: NOV 20 1952
J. J. Zarichak
 Director

Company Stanolind Oil and Gas Company

Address Rangely, Colorado

By L. King

Title Prod. Foreman

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.