

**Proposed Plugging Diagram**

**Well Name: Sealock #1**

**API: 123-10765**

**Location: NWNE 2 4N 68W**

**Lat/Long: 40.346114 / 104.966807**

**Well History:**  
 7/21/19/2 - Spud  
 7/30/82 - TD Reached  
 1/27/83 - J-Sand Completed

12/4/92 - PA Intent filed (J-sand non-commercial)  
 10/29/93 - Original well abandonment

**Original Plugging Details:**  
 CIBP set @ 6715' w/3 sx cement on top, cut off below plow depth & set 10 sx plug @surface & sealed w/ welded cap. The site has been restored.

**Formations:**  
 4077 - Sussex  
 4452 - Shannon  
 6800 - Niobrara  
 7117 - Fort Hays  
 7136 - Codell  
 7588 - J-Sand  
 7633 - Skull Creek

**Proposed Plugging Notes:**  
 No CBL on file for 100 sx set at 1110'. Actual coverage is uncertain.

