



00046206

OIL AND GAS CONSERVATION COMMISSION DEPARTMENT OF NATURAL RESOURCES OF THE STATE OF COLORADO

File in duplicate for Patented and Federal lands.
File in triplicate for State lands.

RECEIVED

JUL 22 1974

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> WATER INJECTION WELL		5. LEASE DESIGNATION AND SERIAL NO. D-033084A
2. NAME OF OPERATOR CHEVRON OIL CO, WESTERN DIVISION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR RANGELY, COLORADO 81648		7. UNIT AGREEMENT NAME RANGELY WEBER SAND
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1592' NSL & 2556' WEL OF SEC. 2, T1N, R102W, At proposed prod. zone 6th P.M. NE SW		8. FARM OR LEASE NAME NEWTON GOVERNMENT
14. PERMIT NO.		9. WELL NO. 1-2
15. ELEVATIONS (Show whether DF, RT, GR, etc.) KB - 5258		10. FIELD AND POOL, OR WILDCAT RANGELY WEBER SAND
		11. SEC., T., E., M., OR BLK. AND SURVEY OR AREA SEC. 2 T1N, R102W
		12. COUNTY RIO BLANCO
		13. STATE COLO

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐

(Other)

PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON ☒CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐

(Other)

REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work AFTER AUGUST 1, 1974

It is proposed to plug and abandon this well as follows:

1. Rig up.
2. This well has a CIBP set at 5900' and one set at 3400', each capped with 2 sacks cement.
3. Pump 150 sacks cement down the 7"-surface pipe annulus.
4. Lay a 30' cement plug in the top of the 7" casing.
5. Weld a plate over casing head and install marker.
6. Remove or bury cement pumping unit foundation and "dead men".
7. Clean up all loose pipe, fittings, debris, etc. from location.
8. Scarify non grassy areas and plant seed (8-10#/acre), avoid further disturbance of surface conditions.

DVR	
FJP	
HHM	
JAM	✓
JJD	✓
BCH	
CCM	

18. I hereby certify that the foregoing is true and correct

SIGNED

J.A. Thompson

TITLE

Unit Supt.

DATE

7-19-74

(This space for Federal or State office use)

DIRECTOR

APPROVED BY

M. Rogers

TITLE

OCCASIONAL COUNSEL

DATE

JUL 24 1974

CONDITIONS OF APPROVAL, IF ANY: