


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator CALDWELL & COVINGTON 12905 Field _____ Wildcat X
Lease Name US Oil & Gas Lease C-0634 Well No. 3 County Rio Blanco
Location SE-SE- SW Section 1 Township 1 N Range 102 W Meridian 6th p.m.
(Quarter Quarter)
100 feet from S Section line and 2070 feet from E Section Line
N or S E or W

TOTAL DEPTH 3577 DATE OF PLUGGING 4-4-60

DETAILS OF WORK

Total depth was 3577': Operator set 120' of 8 5/8" surface casing and cemented from top to bottom. A 6 1/4" hole was drilled from under surface to total depth. A slight show of oil was encountered at 2825-50 feet but was not sufficient to justify completion attempts. Operator received permission to plug and abandon. Hole was filled with mud from TD to 30'. From 30 feet to surface a cement plug was set. A 4" steel marker was set in hole and extends 4' above ground. Location was cleaned and pits filled.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<u>W</u>
JJD	<u>✓</u>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JAN 25 1961Company Caldwell & Covington Date 1-21-61Address P. O. Box 473, Vernal, Ut. Phone No. 1060

Director

By

(Signature)

Title PartnerREMARKS: Lato