

JUL 28 1967

67 301



COLO. OIL & GAS CONS.

5. LEASE DESIGNATION AND SERIAL NO.
COMM.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
C. Jones et al

9. WELL NO.
1

10. FIELD AND POOL, OR WILDCAT
Wildcat

11. SEC., T., R., M., OR BLK.
AND SURVEY OR AREA
11-6N-87W

12. COUNTY OR PARISH
Routt

13. STATE
Colo.

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
DRILL DEEPEN PLUG BACK

b. TYPE OF WELL
OIL WELL GAS WELL OTHER SINGLE ZONE MULTIPLE ZONE

2. NAME OF OPERATOR
Kenneth D. Luff - Martinets - Alpine Oil Co., Inc.
PHONE

3. ADDRESS OF OPERATOR
428 Patterson Building, Denver, Colo. 80202

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)
At surface
676 fel x 1138 fnl*
At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE
4 miles west of Milner, Colorado

15. DISTANCE FROM PROPOSED LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. line, if any) (own offset leases) 676'
16. NO. OF ACRES IN LEASE 160

17. NO. OF ACRES ASSIGNED TO THIS WELL 40

18. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. None
19. PROPOSED DEPTH 5100'

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
6783.75 ung. grd.

22. APPROX. DATE WORK WILL START
July 28, 1967

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
13-3/4"	9-5/8"	32#	60'	75 sacks
8-3/4"	7"	20#	3300'	100 sacks

Plan to drill 13-3/4" hole to approximately 70' and set 60' of 9-5/8" surface pipe. Drill 8-3/4" hole with mud to a depth of approximately 3300' and set 7" casing. Drill 6-1/4" hole with air to a depth at which commercial oil production is encountered or the Carlile shale (approximately 5100') whichever occurs first. If productive will complete as oil well.

*Copies of survey plats will be mailed prior to commencement of drilling.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Kenneth D. Luff TITLE Operator DATE July 24, 1967

(This space for Federal or State office use)

PERMIT NO. 67 301 APPROVAL DATE

APPROVED BY D.V. Rogers TITLE Director DATE JUL 28 1967

CONDITIONS OF APPROVAL, IF ANY:

67-301

See Instructions On Reverse Side

05 107 6002