



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

124

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report. ☒ Abandonment

October 9 19 50

Following is a ~~(notice of intention to do work)~~ (On land)
(report of work done) (patented) described as follows:

Colorado	Morgan	
State	County	Field
<u>1</u>	<u>Lee</u>	<u>12 NW 1/4 NE 1/4 NE 1/4</u>
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)
		<u>2 North</u>
		(Twp.)
		<u>57 West</u>
		(Range) (Meridian)

The Well is located 330 ft. (~~N~~) of North Line and 990 ft. (~~E~~) of East Line
(S) (W)

The elevation above sea level is 1496.11 ft. G.L.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Well was completed October 3, 1950, to a total depth of 5542' in the Dakota Series; extra heavy mud was pumped into well from 5542' to 5450'; 10 sacks of cement placed in hole at 5450'; extra heavy mud in hole to 5420'; 10 sacks cement placed at 5420'; heavy mud to base of surface casing; 10 sacks cement at 180' or base of surface casing; very heavy mud pumped into hole to within 20' of top; 10 sacks cement were used to fill hole to surface; 10' joint of 4" pipe was set in surface plug, 6' being imbedded in cement and 4' above ground as permanent marker. Screw cap was placed on top of pipe. The E. K. Carey Drilling Co., Inc., under the supervision of Joe Hurley, superintendent, drilled, plugged and abandoned the well. A certified copy of the driller's log is attached.

Approved: Oct. 16, 1950
John E. Brown
State Oil Inspector

Company THE DERBY OIL COMPANY
Address Wichita, Kansas
By A. E. Zoller
Title Pres.

Submit reports of proposed work, for approval, on this form in Duplicate.