

OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO

RECEIVED APR 13 1964



00054420

PLUGGING RECORD

OIL & GAS CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Kingwood Oil Company Field Xenia, West Wildcat
Lease Name Xenia, West Unit Well No. 4-1 County Washington
Location NW NE Section 11 Township 2N Range 54W Meridian 6th
650 feet from N Section line and 1980 feet from E Section Line
N or S E or W

TOTAL DEPTH 4880' DATE OF PLUGGING 4-2-64

DETAILS OF WORK

Cast iron bridge plug at 4780'. Plugged back with pea gravel, 4780-4710'. Placed 5-sack cement plug, 4710-4680'. Shot casing loose. Recovered 104 jts., 3271', of 5 1/2" casing. Kept hole full of heavy mud. Placed 10 sacks of cement, 132' to 102'; mud, 102' to 30'; 5 sacks of cement, 30' to surface.

Left 1608' of 5 1/2", 15.5# casing in hole, 3271' to 4879'.

Left 132' of 8-5/8", 15# surface casing in hole.

Handwritten note: 7/24/64 Loc. revealed ok. appears 77.



Table with 2 columns and 7 rows: DVR, WRS, HHM, JAM, FJP (checked), JJD (checked), FILE

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: Date APR 14 1964
Company Kingwood Oil Company Date 4-6-64
Address 1470 First National Building
Phone No. CE 6-3771
By Ben Spain (Signature) Title Chief Clerk