


OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO



OIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS



Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Wytex Oil Corporation Field Pinneo Wilcat
 Lease Name Government #02258 Well No. 3-15 County Morgan
 Location NW SE Section 15 Township 2N Range 55W Meridian 6th
 (Quarter Quarter)
1980 feet from S Section line and 1939 feet from E Section Line
 Nor S E or W

TOTAL DEPTH 5091'DATE OF PLUGGING 10-2-56

DETAILS OF WORK

Spudded 9-26-56, ran 4jts of 8-5/8" surface casing set 136' KBand cemented with 125 sacks of regular cement.

After encountering no shows of commercial value in the geological column. Method of plugging will be as follows: a cement plug will be spotted through the D and J sands and below and in the 8-5/8" casings the remaining hole was felled with heavy rotary mud and a steel cap and marker will be erected.

Subject well was plugged and abandoned in the following manner: 25 sack cement plug was placed through the D and J sand, and a 10 sack plug placed below and in the 8-5/8" casing. A steel cap and marker were then welded over the hole. Spotted plug covered the zone from 5090' to 4965'.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	✓
FILE	

The above information is copied from the reports sent the Geological Survey Department.

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUL 23 1958

Director

Company Wytex Oil Corporation Date 7-21-5890 State StreetAddress Albany 7, New YorkPhone No. 3-7174

By

(Signature)

Title Agent