



00054507

OIL AND GAS CONSERVATION COMMISSION
DEPARTMENT OF NATURAL RESOURCES
OF THE STATE OF COLORADO

File in duplicate for Patented and Federal lands.
 File in triplicate for State lands.

RECEIVED

MAY 22 1980

COLO. OIL & GAS CONS. COMM.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
 Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. L-2595	
2. NAME OF OPERATOR EXETER EXPLORATION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME -	
3. ADDRESS OF OPERATOR P. O. Box 17349, Denver, CO 80217 TA		7. UNIT AGREEMENT NAME -	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 661' FSL & 1987' FEL (SWSE) At proposed prod. zone Same		8. FARM OR LEASE NAME GEBAUER	
14. PERMIT NO. -		9. WELL NO. # 1-A (or #2A) (or #2)	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4555' KB		10. FIELD AND POOL, OR WILDCAT Ruby	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Section 28, 2N-54W (SWSE)	
		12. COUNTY Washington	13. STATE CO

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input type="checkbox"/>
(Other) <input checked="" type="checkbox"/> TEMPORARY ABANDONMENT	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work 4-4-80

This well has been producing from the "D" Sand (4852-55') since January, 1960. Casing problems developed in this well from about 650-1950 feet. On 3-27-80, a service unit was moved to location. 3/4" rods were found to be parted at 3350', with the 2" tubing full of drilling mud. On 4-3-80 a 4-1/2" Baker mechanical set Model "N" cast iron bridge plug was run on 2" tubing, hydrotested to 6000# while going into the hole. The BP was set at 4729' (above the "D" Sand). The 2" tubing was pulled and laid down. A dump bailer was run, with 1 sx of cement (approximately 10') dumped on top of the BP.

This well was T.A.'d on 4-4-80.

DVR	<input checked="" type="checkbox"/>
F&P	<input checked="" type="checkbox"/>
HMM	<input checked="" type="checkbox"/>
JAM	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
RLS	<input checked="" type="checkbox"/>
OSM	<input checked="" type="checkbox"/>

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature]TITLE Vice President-ProductionDATE 5-20-80

(This space for Federal or State office use)

APPROVED BY [Signature]
CONDITIONS OF APPROVAL, IF ANY:TITLE DIRECTOR
O&G CONS. COMM.DATE MAY 23 1980

16

file