



00054506

DEPARTMENT OF NATURAL RESOURCES OF THE STATE OF COLORADO

File in duplicate for Patented and Federal lands. File in triplicate for State lands.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT-" for such proposals.)

1. OIL WELL [] GAS WELL [XXXX] OTHER []
2. NAME OF OPERATOR: EXETER EXPLORATION COMPANY
3. ADDRESS OF OPERATOR: P. O. Box 17349, Denver, CO 80217
4. LOCATION OF WELL: 661' FSL & 1987' FEL (SWSE)
14. PERMIT NO.: -
15. ELEVATIONS: 4555'

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data
NOTICE OF INTENTION TO: TEST WATER SHUT-OFF [], PULL OR ALTER CASING [], etc.
SUBSEQUENT REPORT OF: WATER SHUT-OFF [], REPAIRING WELL [], etc.

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work.)

Date of work: May

This well has been producing from the "D" Sand (4852-55') since January, 1960. Casing problems developed in this well from about 650-1950'. On 3-27-80, a service unit was moved to location. 3/4" rods were found to be parted at 3350' with the 2" tubing full of drilling mud. On 4-3-80 a 4-1/2" Baker mechanical set Model "N" cast iron bridge plug was run on 2" tubing, hydro-tested to 6000# while going into the hole. The BP was set at 4729' (above the "D" Sand). The 2" tubing was pulled and laid down. A dump bailer was run, with 1 sx of cement (approximately 10') dumped on top of the BP.

ret. for signature 9-11-80

18. I hereby certify that the foregoing is true and correct
SIGNED: Walt Pearson TITLE: Manager of Engineering DATE: 8-6-80
APPROVED BY: _____ TITLE: _____ DATE: _____

DVR
FJF
HFD
JAW
JJD
RLS
CGM