

OIL AND GAS CONSERVATION COMMISSION  
DEPARTMENT OF NATURAL RESOURCES  
OF THE STATE OF COLORADO

RECEIVED  
OCT 8 1980



00054505

File in duplicate for Patented and Federal lands.  
File in triplicate for State lands.

COLO. OIL & GAS CON. COMM. L-2595

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL  GAS WELL  OTHER

2. NAME OF OPERATOR  
EXETER EXPLORATION COMPANY

3. ADDRESS OF OPERATOR  
P. O. Box 17349, Denver CO 80217

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.  
See also space 17 below.)  
At surface  
661' FSL & 1987' FEL (SWSE)  
At proposed prod. zone  
Same

14. PERMIT NO. - 15. ELEVATIONS (Show whether DF, RT, GR, etc.)  
4555'

5. LEASE DESIGNATION AND SERIAL NO.  
6. IF INDIAN, ALLOTTEE OR TRIBE NAME  
7. UNIT AGREEMENT NAME  
8. FARM OR LEASE NAME  
Gebauer  
9. WELL NO. (Or #2A)  
#1-A (Or # 2)  
10. FIELD AND POOL, OR WELDCAT  
Rubu  
11. SEC., T., R., M., OR BLM. AND SURVEY OR AREA  
SWSE, Sec. 28, 2N-54W  
12. COUNTY Washington 13. STATE CO

RECEIVED  
FEB 5 1982

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input checked="" type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <input type="checkbox"/>	(Other) <input type="checkbox"/>

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work 9-23-80

This well had been producing from the "D" Sand (4852-55') since January, 1960. Casing problems developed in this well from about 650-1950'. On 3-27-80, a service unit was moved to location. 3/4" rods were found to be parted at 3350', with the 2" tubing full of drilling mud. On 4-3-80 a 4-1/2" Baker mechanical set Model "N" cast iron BP was run on the 2" tubing, hydrotested to 6000# while going into the hole. The BP was set at 4729' (above the "D" Sand). The 2" tubing was pulled and laid down. A dump bailer was run with 1 sx of cement (approximately 10') dumped on top of the BP. The well was T.A.'d on 4-4-80.

On 9-22-80, the following work was performed: 1. Pushed Halliburton 4-1/2" plug down the 4-1/2" casing to 160'. Dumped 3 gallons cement on top of plug. Let set overnight. On 9-23-80, the 4-1/2" casing was filled from 160' to surface with 17 sxs common cement. WELL IS P.A.'d (9-23-80)

18. I hereby certify that the foregoing is true and correct

SIGNED Wayren K. Arnold TITLE Vice President - Production DATE 10-1-80.

(This space for Federal or State office use)

APPROVED BY [Signature] TITLE DIRECTOR DATE OCT 24 1980  
G & G CON. COMM.

CONDITIONS OF APPROVAL, IF ANY:

DVR
FJP
HJM
JAM
JJD
RLS
CGM