




00238620

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete

☐

Report of Remedial Work

☐

Notice of Intention to Change Plans

☐

Report of Recompletion

☐

Notice of Intention to Abandon Well

☒

Other

☐

(Check appropriate space)

LEASE NAME J. F. Kirk "A" WELL NO. 6FIELD Walker WILDCAT COUNTY LoganLOCATION NW NE SE Section 17 Township 9N Range 53W Meridian 6th P.M.330 feet from N Section Line and 994 feet from E Section Line of SE/4
N or S E or W

(DETAILS OF WORK)

J. F. Kirk "A" 6 was completed during November, 1952 pumping 49 barrels oil and 5 barrels water from Dakota sandstone perforations 4895 (-786) to 4901 (-792) feet. Production declined rapidly, and water appeared during November, 1955 after an acid and controlflow treatment. During January, 1959, the well produced a daily rate of 1 barrel oil and 20 barrels water. During February, 1959, the well ceased to pump, and a fluid level was shot which found approximately 4200 feet of fluid above the pump. This fluid is assumed to be largely water since the water cut in February, 1959 was approximately 95 per cent. Based on these experiences, we propose to plug and abandon J. F. Kirk "A" 6.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Date

APR 17 1959

Director

Company Shell Oil Company
1845 Sherman Street
Address Denver 3, ColoradoDate 4/15/59Phone No. AC 2-8454By L. W. Elderkin
(Signature) L. W. ElderkinTitle Division
Production
Superint.