

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



226

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report X.....

Following is a (notice of intention to do work) (On land) February 19, 19 52
(report of work done) (patented) described as follows:

Colorado	Logan	Walker			
State	County	Field			
4	J. F. Kirk	SE/4 Section 17	9N	53W	
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)	(Twp.)	(Range)	(Meridian)
The well is located 990 ft. (N) of S Line and 990 ft. (E) of E Line (W)					

The elevation above sea level is 4137 DF ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- 12-15-51 Spudded and cemented 8 5/8" at 258' with 150 sacks.
- 12-26-51 Total depth 5000'. DST No. 1 4920-30, gas to surface 3 minutes, flowed 38 bbls. oil per hr. Ran Schlumberger. Cemented 4 1/2" at 4984 with 200 sacks.
- 1-10-52 Perforated 4926-29 with 12 - 10 gram jets.
- 1-14-52 Flowed 238 bbls. oil, trace water, 24 hours.
- 1-21-52 Flowed 204 bbls. oil, no water, 24 hours. COMPLETE

Schlumberger Tops: Niobrara 3955, Timpas 4269, Greenhorn 4512, 'Muddy' 4769, Dakota 4871.

Approved: FEB 21 1952
State Oil Inspector
DIRECTOR

Company Shell Oil Company
Address Denham Bldg., Denver 2, Colorado
By
Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate.