


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOOIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Shell Oil Company Field Walker Wilcat
Lease Name J. F. Kirk Well No. 4 County Logan
Location NW SE SE Section 17 Township 9N Range 53W Meridian 6th
(Quarter Quarter)
990 feet from S Section line and 990 feet from E Section Line
N or S E or W

No Prior Approval

TOTAL DEPTH 5,000DATE OF PLUGGING 5-23-60

DETAILS OF WORK

Plugged well as follows:

Contractor: Donnelly Casing Pulling Unit

Dumped sand from 4954 to 4904 feet. Dumped five sacks of cement to 4853 feet. Shot casing at 3705 feet. Pulled 138 joints 4-1/2", 15.21# casing. Set rock bridge at 250 feet. Dumped ten sacks of cement to 223 feet and mudded to 18 feet. Dumped five sacks of cement to top of surface.

Sold to Hargus Tool Rental in place.

| | |
|------|-------------------------------------|
| AJJ | |
| DVR | |
| WRS | |
| HHM | |
| JAM | |
| FJP | |
| JJD | <input checked="" type="checkbox"/> |
| FILE | |

05-075-06491
p & a oil

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Company Shell Oil CompanyDate 6-22-60

Date

Address 1845 Sherman St., Denver 3, ColoradoPhone No. Ac 2-8454

Director

By

(Signature)

Title SuperintendentFor: L. W. ElderkinVIOLATION
REMARKS: