

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



1 approved copy
returned 9-5-51
LB
174

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report..... X

Following is a (~~notice of intention to do work~~) (On land) August 31 1951
(report of work done) (~~notice of~~) described as follows:

Colorado	Logan	Walker			
State	County	Field			
1	J. F. Kirk	SE/4-17	9N	53W	
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)	(Twp.)	(Range)	(Meridian)

The well is located 330' ft. (N) of South Line and 330' ft. (E) of East
Line (S) (W)

The elevation above sea level is 4138 ft. D.F.

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)

7-21-51 Drill stem test No. 1 4926-4938 Open 1 hour. Flowed by heads
an estimated 40 bbls. oil per hour.

7-23-51 Ran Schlumberger log to TD at 5033, Tops:

Niobrara 3965

Greenhorn 4510

'Muddy' 4766

Dakota 4870

5025' of 4 $\frac{1}{2}$ " 9 $\frac{1}{2}$ " casing cemented at 5031 with 250 sacks.

8- 2-51 Perf. 4927-32 with 20 jet shots.

8-17-51 Flow 185 barrels oil and no water in 16 hours through 8/64" choke,
GOR 240.
Complete

Approved: Sept 4 1951

State Oil Inspector

Company SHELL OIL COMPANY
413 Denham Building
Address Denver 2, Colorado

By

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate.