



**OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO**



SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input checked="" type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME J. F. Kirk "A" WELL NO. 1

FIELD Walker WILDCAT COUNTY Logan

LOCATION SE SE SE Section 17 Township 9N Range 53W Meridian 6th P.M.
 (Quarter Quarter)

330 feet from S Section Line and 330 feet from E Section Line
 N or S E or W

(DETAILS OF WORK)

6-29-57 Moved in and rigged up cable tools. Pulled rods and 135 joints tubing.

6-30-57 Pulled 31 joints tubing. Check PBTD and set bridge plug at 4820 feet and capped with eight feet of cement. Checked cement top at 4812 feet and perforated 4768 to 4774 feet with four 21 gram jets per foot. Ran 161 joints 2" tubing to 4810 feet. Started swabbing well at 21:00 MST.

7-1-57 Swabbed well until 01:00 MST. Total fluid swabbed 30 barrels. Well flowed 14 barrels fluid in four hours with some gas. Tubing pressure 100 psi, casing pressure 300 psi.

7-2-57 Flowing on test.

7-3-57 On 24 hour test ending 7-3-57, well flowed 1250 MCF through .750 inch choke with 3.2 barrels distillate and one barrel water.

PBTD 4812 feet

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

OCT - 2 1957

Date

Director

Company Shell Oil Company

Date 10-1-57

Address 1845 Sherman Street

Phone No. AComa 2-8454

By L. W. Elderkin
 (Signature)

Title Division Prod. Supt.