



00091667

DAILY REPORT DETAILED

RECEIVED

JUL 31 1978

COLO. OIL & GAS CONS. COMM

LEASE Peterson "F" WELL NO. 1 SHEET NO. 3

DATE	TOTAL DEPTH	NATURE OF WORK PERFORMED
------	----------------	--------------------------

1978
July

11

PETERSON F NO. 1 PBTD 5162. TSTG, NO REPORT..

12

PETERSON F NO. 1 PBTD 5162. NO TEST, APPARENT DOWNHOLE PROBLEMS.
WILL TEMPORARY DROP PENDING MI PULLING UNIT AND CHANGING PUMP..July
14

PETERSON F. NO. 1 PBTD 5162. PU FROM TEMP. DROPPED 7/12/78.
MI PULLING UNIT, CHANGED PUMP. STARTED WELL PMPG. PMPD 24 HRS,
REC 5 BO, 35 BW. FINAL REPORT SUMMARY. PERFORATED LOWER D SAND
5098-5102 FT W/4 SPF, TOTAL 17 SHOTS, HYPERJET. ACIDIZED LOWER
ZONE W/500 GAL 15 PERCENT HCL. ACIDIZED UPPER D SAND PERFS
5078-82 FT W/1000 GAL 15 PERCENT HCL. RETURNED TO A PUMPING OIL
WELL FROM D SAND PERFS 5078-5102 FT OA IN THE STAGECOACH FIELD,
MORGAN COUNTY, COLORADO, WITH A FINAL TEST OF 5 BOPD, 35 BWPD.
FINAL REPORT..