


OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

## UNDRY NOTICES AND REPORTS ON WELLS



## INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☒Other ☐

(Check appropriate space)

LEASE NAME Madera Federal WELL NO. 3FIELD \_\_\_\_\_ WILDCAT X COUNTY MoffatLOCATION NW NW Section 8 Township 9N Range 90W Meridian 6th  
(Quarter Quarter)660' feet from North Section Line and 660' feet from West Section Line  
N or S E or W

## (DETAILS OF WORK)

TD 5000'.

Spudded 9-12-60. Set 8-5/8" csg @229' w/150 sx reg bulk cem. Drld to TD without encountering commercial production. With hole full of mud, it is proposed to spot cement through drill pipe as follows:

2670'-2760'	25 sx
1825'-1900'	25 sx
190' - 250'	25 sx

Well to be capped w/10 sx cem to top of surface pipe, dry hole marker installed and location restored.

✓ Verbal approval to plug received from Mr. Frazier, USGS, and Mr. Smith, State of Colorado.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

OCT - 3 1960

Date

Director

Company Gulf Oil Corporation  
Production DepartmentDate 9-28-60Address Box 1346  
Salt Lake City, UtahPhone No. ELgin 5-7547By [Signature]  
(Signature)Title Area Prod. Manager