


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

PLUGGING RECORD



INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator PLAINS EXPLORATION COMPANY Field Wildcat x
 Lease Name Orville H. Craig Well No. 1 County Morgan
 Location C NW SW Section 13 Township 2N Range 55W Meridian 6th P.M.
 (Quarter Quarter)
1980 feet from S Section line and 650 feet from W Section Line
N or S E or W

TOTAL DEPTH 5160'DATE OF PLUGGING April 22, 1961

DETAILS OF WORK

The well was plugged April 22, 1961, by filling it with heavy mud from the total depth to the bottom of the surface pipe (5160-130). A 10 sack cement plug was set in the bottom 30 feet of the surface pipe 130-100, then the casing was filled with heavy mud to within 20 feet of the top. A 7 sack cement plug was set in the top 20 feet of the surface pipe (32-12).

All measurements are taken from the kelly bushing, which was approximately 9 feet above the ground.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date APR 25 1961

Director

Company PLAINS EXPLORATION COMPANY Date 4-24-61
1135 Petroleum Club Bldg.Address Denver 2, Colorado Phone No. CH 4-7431By Russell H. Volk Title President(Signature)
Russell H. Volk